

FORM
5Rev
02/08

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400273847

Date Received:

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 10071

4. Contact Name: Julie Webb

2. Name of Operator: BARRETT CORPORATION* BILL

Phone: (303) 312-8714

3. Address: 1099 18TH ST STE 2300

Fax: (303) 291-0420

City: DENVER State: CO Zip: 80202

5. API Number 05-045-19243-00

6. County: GARFIELD

7. Well Name: Werner

Well Number: 33C-23-692

8. Location: QtrQtr: SWSE Section: 23 Township: 6S Range: 92W Meridian: 6

Footage at surface: Distance: 873 feet Direction: FSL Distance: 1536 feet Direction: FEL

As Drilled Latitude: 39.507814 As Drilled Longitude: -107.630257

GPS Data:

Data of Measurement: 08/04/2010 PDOP Reading: 6.0 GPS Instrument Operator's Name: T. Barnett

** If directional footage at Top of Prod. Zone Dist.: 2080 feet. Direction: FSL Dist.: 1988 feet. Direction: FEL

Sec: 23 Twp: 6S Rng: 92W

** If directional footage at Bottom Hole Dist.: 2075 feet. Direction: FSL Dist.: 2009 feet. Direction: FEL

Sec: 23 Twp: 6S Rng: 92W

9. Field Name: MAMM CREEK

10. Field Number: 52500

11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 07/19/2012 13. Date TD: 02/16/2012 14. Date Casing Set or D&A: 02/17/2012

15. Well Classification:

☐ Dry ☐ Oil ☒ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 7908 TVD** 7696 17 Plug Back Total Depth MD 7856 TVD** 6347

18. Elevations GR 5950 KB 5973

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

CBL, Mud, Temp, Triple Combo

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	26	16	42	0	40		0	40	CALC
SURF	12+1/4	9+5/8	36	0	805	240	0	820	CALC
1ST	7+7/8	4+1/2	11.6	0	7,902	592	4,720	7,908	CBL

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
WILLIAMS FORK	3,909		<input type="checkbox"/>	<input type="checkbox"/>	
ROLLINS	7,605		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

The 72 Hour Bradenhead Pressure Test was 0 psig. Conductor was cemented with grout. 8 3/4 hole size was used to drill from bottom of surface casing to 5765' then 7 7/8 hole size was used to drill to TD.
As drilled GPS is taken from conductor. Surface casing is set with Air rig.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Julie Webb

Title: Permit Analyst

Date:

Email: jwebb@billbarrettcorp.com

Attachment Check List

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
	CMT Summary *	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
400273865	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
400273866	LAS-MUD	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400273867	LAS-CEMENT BOND	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400273869	LAS-TEMPERATURE	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400273871	LAS-TRIPLE COMBINATION	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400301905	DIRECTIONAL DATA	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

General Comments

User Group	Comment	Comment Date
------------	---------	--------------

--	--	--

Total: 0 comment(s)