

WESTERN WELLSITE SERVICES, LLC
17509 County Road 14,
Ft. Morgan, Colorado 80701
(970)-867-9007 or (970)-867-8374 (Fax)

Job Log

Date: 6-5-12

Operator: Encana Oil and Gas

Well name: Evacuation Creek 7607, *API # 05-103-08551*

Rio Blanco County, Colorado

MIRU, NUBOP

Lay down 120 jts of tubing

RU wireline, Run gauge ring to 3,850', RIH with CIBP
and set at 3,784', dump bail 35' of cement on plug

Load hole and pressure test casing, failed

TIH with packer and isolate leak at 842', TOH

TIH to 842'

Pump 270 sxs of cement, TOH, WOC,

Tag with wireline at 930'

Pressure test casing, failed

WOC overnight for cement to set

TIH and tag at 865', pressure test casing held

Perforate at 762'

Pump 54 sxs of cement, WOC, and tag at 468'

RIH to 100' and circulate cement to surface

Top fill annulus with 12 sxs

Cut off wellhead

Weld a steel plate

RDMO

All cement is 15.8# class G neat

Cementing contractor: Magna Energy Services, LLC

Cementing contractor supervisor: Jeremy Rose

Operator supervisor: Brent Huckins, Cary Huckins

BLM supervisor: Steve Halcomb

Wireline contractor: Magna Energy Services, LLC