

FORM
2

Rev
12/05

State of Colorado Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400301990

Date Received:

APPLICATION FOR PERMIT TO:

1. Drill, Deepen, Re-enter, Recomplete and Operate

2. TYPE OF WELL

OIL GAS COALBED OTHER _____
SINGLE ZONE MULTIPLE COMMINGLE

Refiling

Sidetrack

PluggingBond SuretyID

20100017

3. Name of Operator: ENCANA OIL & GAS (USA) INC

4. COGCC Operator Number: 100185

5. Address: 370 17TH ST STE 1700

City: DENVER State: CO Zip: 80202-5632

6. Contact Name: Heather Mitchell Phone: (720)876-3070 Fax: (720)876-4070

Email: heather.mitchell@encana.com

7. Well Name: Latham DHS Well Number: 4C-13 O12 8100

8. Unit Name (if appl): Mckay Fork Unit Unit Number: 75338X

9. Proposed Total Measured Depth: 12559

WELL LOCATION INFORMATION

10. QtrQtr: 4 Sec: 12 Twp: 8S Rng: 100W Meridian: 6

Latitude: 39.370708 Longitude: -108.492900

Footage at Surface: 1060 feet FNL/FSL FSL 519 feet FEL/FWL FEL

11. Field Name: Wildcat Field Number: 99999

12. Ground Elevation: 6725 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 04/14/2012 PDOP Reading: 1.3 Instrument Operator's Name: Ben Johnson

15. If well is Directional Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 394 FSL 1987 FWL _____ Bottom Hole: FNL/FSL 650 FSL 1980 FWL _____
Sec: 12 Twp: 8S Rng: 100 W _____ Sec: 13 Twp: 8S Rng: 100 W _____

16. Is location in a high density area? (Rule 603b)? Yes No

17. Distance to the nearest building, public road, above ground utility or railroad: 1260 ft

18. Distance to nearest property line: 259 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 1327 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Mancos	MNCS			

21. Mineral Ownership: Fee State Federal Indian Lease #: _____

22. Surface Ownership: Fee State Federal Indian

23. Is the Surface Owner also the Mineral Owner? Yes No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? Yes No

23b. If 23 is No: Surface Owners Agreement Attached or \$25,000 Blanket Surface Bond \$2,000 Surface Bond \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

Fee OGL (SHL OGL and part of wellbore path) - 8S-99W-Sec. 17: Resurvey Tract 47, Section 18: Tracts 46 and 47 T8S-R100W-Sec. 10: N/2SE, SESE Sec. 11: N/2S/2, SWSW Sec. 12: Lot 4, S/2SW Sec. 13: Lot 1, NENW COC 13423 - T8S-R100W-Sec. 13: NWNW, S/2NW COC 12750 (final BHL) - T8S-R99W-Sec. 18: Lots 11, 12, 13, 14, 15, 17, 18, 19, 20, 21, 22, 23, 24, E/2SW, S/2SE T8S-R100W-Sec. 11: SESW, S/2SE, Sec. 13: Lots 3, 4, SW Sec. 14: E/2W/2, E/2

25. Distance to Nearest Mineral Lease Line: 1977 ft 26. Total Acres in Lease: 1243

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? Yes No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? Yes No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? Yes No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? Yes No

31. Mud disposal: Offsite Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: Land Farming Land Spreading Disposal Facility Other: Recycle and bury

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	30	20	Line Pipe	0	120	319	120	0
SURF	14+3/4	10+3/4	40.5	0	1,000	469	1,000	0
2ND	9+7/8	7+5/8	26.4	0	6,171	715	6,171	
3RD	6+3/4	4+1/2	12	0	12,559	574	12,559	

32. BOP Equipment Type: Annular Preventer Double Ram Rotating Head None

33. Comments Distance in #17 is from the nearest road. The surface is fee and minerals are fee/fed. The conductor and surface casing are run to surface. The 2nd string is cemented 200' above TOG. The 3rd string is cemented 200' into the second string. The 3rd string is tapered, 5 1/2 & 4 1/2

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan? Yes No

36. Is this application part of submitted Oil and Gas Location Assessment? Yes No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Heather Mitchell

Title: Regulatory Analyst Date: _____ Email: heather.mitchell@encana.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

API NUMBER

05

Permit Number: _____ Expiration Date: _____

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Attachment Check List

Att Doc Num	Name
400302002	DEVIATED DRILLING PLAN
400302003	WELL LOCATION PLAT
400302004	DIRECTIONAL DATA

Total Attach: 3 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)