



# CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600245

Date <u>11/24/11</u>	Well Owner <u>Kerr McGee</u>	Well No <u>28W-25H2</u>	Lease <u>Camp</u>
County <u>Weld</u>	State <u>Colorado</u>		
Charge to <u>Kerr McGee Oil &amp; Gas Onshore, LP</u>			
Address <u>1999 Broadway, Suite 3700 (MAJOR #44)</u>			
City, State Zip <u>Denver, Colorado 80202</u>			
Type of Job	Depth	Fl. <u>871</u>	
<u>Surface</u>	<u>9 5/8" CG-36" 12 1/4" lbk</u>	Bottom of Surface	Fl. <u>865</u>
Plug	Plug Landed @ <u>821</u>	Fl.	Time On <u>1600</u>
Production	Pipe Landed @ <u>865</u>	Fl.	Plug Down <u>1900</u>

Description	Qty.	Meas.
Set Up Charge		
Cement Neat <u>✓ Type III</u>	<u>420</u>	SKS
Poz. Mix		
Calcium Chloride	<u>2.5</u>	%
Gel % Flo: Cete 1/4 # Per Sack		
Mileage Charge	<u>132</u>	Miles
Fuel Surcharge <u>2061480. DR</u>	<u>132</u>	Miles
Additional Cement <u>80012090</u>		SKS
Mixing Rate <u>4 BPM</u>	Pre-Flush	<u>1820</u> <u>1826</u>
Disp. Rate <u>5 BPM</u>	Mixing	<u>1826</u> <u>1844</u>
Slurry Vol. <u>1.32 Cu. Ft./Sk</u>	Change Valves	<u>1844</u> <u>1847</u>
Slurry Wt. <u>14.8 - 15.0 PPG</u>	Displacement	<u>1847</u> <u>1900</u>
Water/Cement <u>6.25 Gal/SK</u>		
Water Temp. <u>57°F</u>		
Total Slurry Vol. <u>98.7</u>	BBL'S Cement	
Landed Plug @ <u>820</u>	PSI/Final Lift @ <u>400</u>	PSI
Pre-Flush W/ <u>30</u>	BBL'S H <sub>2</sub> O	Tax Reference Code
Displace W/ <u>63.4</u>	BBL'S H <sub>2</sub> O	State <u>CO 2.9%</u>
Circulate <u>5</u>	BBL'S Cement	Total