



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600563

Date	7/1/12	Well Owner	Kerr McGee	Well No.	1-2	Lease	Lambrecht
County	Weld	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (Xtreme II)						
City, State Zip	Denver, Colorado 80202						
Type of Job			Depth	Ft. 960			
Surface	8 5/8" CSG 24"		Bottom of Surface	Ft. 949			
Plug			Plug Landed @	905	Ft.	Time On	1730
Production			Pipe Landed @	960	Ft.	Plug Down	0115
Description	Qty.	Meas.	Unit Price	Amount			
Set Up Charge	1						
Cement Neat TYPE III Duaine Bell	600	SKS					
Poz. Mix							
Calcium Chloride User ID ZDSB4	2.5	%					
Gel % Fio-Cele 1/4" 4-Per Sec	204	6011					
Mileage Charge	180	Miles					
Fuel Surcharge	180	miles					
Additional Cement		SKS					
Mixing Rate	4 BPM	Pre-Flush	0022	0026			
Disp. Rate	5 BPM	Mixing	0026	0101			
Slurry Vol.	1.32 Cu.Ft./Sk	Change Valves	0101	0104			
Slurry Wt.	14.8 - 15.0 PPG	Displacement	0104	0115			
Water/Cement	6.25 Gal/SK						
Water Temp.	71°F						
Total Slurry Vol.	141.0	BBLS Cement					
Landed Plug @	325	PSI/Final Lift @	450	PSI			
Pre-Flush Wt	20	RRI S H ₂ O	Tax Reference Code	Sub Total			
Displace Wt	57.5	BBLS H ₂ O	State CO 2.9%	Tax			
Circulate	5	BBLS Cement		Total			
Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1201		Pump Truck		60			
1244/1216		Bulk Truck		60/60			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Jim Adams, Chris, Marco

Received By

[Signature]
Customer or His Agent