

FORM

2

Rev
12/05

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400283888

Date Received:

05/14/2012

PluggingBond SuretyID

20100017

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
 SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refiling ☐Sidetrack ☐3. Name of Operator: ENCANA OIL & GAS (USA) INC4. COGCC Operator Number: 1001855. Address: 370 17TH ST STE 1700City: DENVER State: CO Zip: 80202-56326. Contact Name: Bonnie Lamond Phone: (720)876-5156 Fax: (720)876-6177Email: bonnie.lamond@encana.com7. Well Name: Shideler Fee Well Number: 31-6D (K31E)8. Unit Name (if appl): Hunter Mesa Unit Number: COC055972

X

9. Proposed Total Measured Depth: 8430

WELL LOCATION INFORMATION

10. QtrQtr: NESW Sec: 31 Twp: 7S Rng: 92W Meridian: 6Latitude: 39.401787 Longitude: -107.708985

Footage at Surface: 2195 feet FNL/FSL FSL 1420 feet FEL/FWL FWL

11. Field Name: Mamm Creek Field Number: 5250012. Ground Elevation: 6899 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 11/13/2010 PDOP Reading: 2.5 Instrument Operator's Name: C.D. Slaugh15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 2180 FNL 1886 FWL 2180 FNL 1886 FWL
 Bottom Hole: FNL/FSL 2180 FNL 1886 FWL
 Sec: 31 Twp: 7S Rng: 92W Sec: 31 Twp: 7S Rng: 92W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No17. Distance to the nearest building, public road, above ground utility or railroad: 715 ft18. Distance to nearest property line: 2740 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 340 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Williams Fork	WMFK			

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#:23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No23b. If 23 is No: ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

T8S-R92W SEC 6: LOTS 1& 2, S2NW; T7S-R92W SEC 31: LOTS 1& 2, E2W2, E2 (ALL)

25. Distance to Nearest Mineral Lease Line: 1886 ft

26. Total Acres in Lease: 660

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☐ Offsite ☒ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	16	20	Linepipe	0	40	5	40	0
SURF	12+1/4	9+5/8	36	0	1,500	461	1,500	0
1ST	7+7/8	4+1/2	11.6	0	8,430	561	8,430	0

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments The top of production will be 500' above TOG

34. Location ID: 324267

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Bonnie Lamond

Title: Permitting Technician Date: 5/14/2012 Email: bonnie.lamond@encana.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved:  Director of COGCC Date: 7/9/2012

API NUMBER

05 045 21631 00

Permit Number: _____ Expiration Date: 7/8/2014

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.

2) GARFIELD COUNTY RULISON FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE

3) NEW MAMM CREEK FIELD NOTICE TO OPERATORS APPLIES TO THIS WELL. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE

4) COMPLIANCE WITH THE NOTICE TO OPERATORS DRILLING WELLS IN THE BUZZARD, MAMM CREEK, AND RULISON FIELDS, GARFIELD COUNTY AND MESA COUNTY – PROCEDURES AND SUBMITTAL REQUIREMENTS FOR COMPLIANCE WITH COGCC ORDER NOS. 1-107, 139-56, 191-22, AND 369-2 (JULY 8, 2010) -- IS REQUIRED. SEE ATTACHED NOTICE.

5) CEMENT ON PRODUCTION CASING MUST BE A MINIMUM OF 200' ABOVE THE TOP OF THE MESA VERDE FORMATION (OR 200' ABOVE THE OHIO CREEK FORMATION IF PRESENT). CEMENT TOP VERIFICATION BY CBL IS REQUIRED. THIS REQUIREMENT SHALL SUPERSEDE THE TOP OF CEMENT REQUIREMENTS IN THE NEW MAMM CREEK FIELD NOTICE TO OPERATORS.

6) THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1 MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 000 FEET DEEP.

Attachment Check List

Att Doc Num	Name
400283888	FORM 2 SUBMITTED
400283890	30 DAY NOTICE LETTER
400283893	WELL LOCATION PLAT
400283894	DEVIATED DRILLING PLAN
400283895	DIRECTIONAL DATA
400284142	SURFACE AGRMT/SURETY

Total Attach: 6 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	No LGD or public comments. Final Review--passed.	6/29/2012 8:32:11 AM
Permit	Per oper, changed dist. to prop. to 2740 and #17 to 715'.	6/28/2012 12:55:46 PM
LGD	Passed DB	5/29/2012 10:18:25 AM
Permit	Operator corrected plugging bond and #22b. This form has passed completeness.	5/14/2012 2:25:05 PM
Permit	Returned to draft. Missing plugging bond and #22b.	5/14/2012 12:09:50 PM

Total: 5 comment(s)

BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)