



# CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

## 600328

NORTHGLENN

Date	1-22-12	Well Owner	Kerr McGee	Well No.	15-36	Lease	STATE
County	WELD	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (XTREME-11)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth	FL 1045				
Surface	8 5/8" CSG-24 #	Bottom of Surface	FL 1035				
Plug		Plug Landed @	990	FL	Time On	2330	
Production		Pipe Landed @	1035	FL	Plug Down	0245	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat TYPE III 100% EXCESS	650	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Cete 1/4 # Per Sack				
Mileage Charge	240	Miles		
Fuel Surcharge	240	miles		
Additional Cement	40	SKS		
Mixing Rate	4 BPM	Pre-Flush	0141	0149
Disp. Rate	5 BPM	Mixing	0149	0149
Slurry Vol.	1.32 <sup>3</sup> Cu.Ft./Sk	Change Valves	0229	0232
Slurry Wt.	14.8 - 15.0 PPG	Displacement	0232	0245
Water/Cement	6.25 Gal/SK		WBS/WO/CC	2051210
Water Temp.	42°F		G/L Acct.	80012090 DRLG
Total Slurry Vol.	162.8	BBS Cement		
Landed Plug @	900	PSI/Final Lift @	400	PSI
Pre-Flush W/	30	BBS H <sub>2</sub> O	Tax Reforomoo Gado	Sub Total
Displace W/	62.9	BBS H <sub>2</sub> O	State CO 2.9%	Tax
Circulate	1	BBS Cement		Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1202		Pump Truck		80			
1214/1218		Bulk Truck		80/80			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By JOE, JOSH, ERNIE, ART

Received By J. Benjamin  
Customer or His Agent