



# CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

## 600526

Date	5/21/12	Well Owner	Kerr McGee	Well No.	8-30	Lease	overlook
County	Weld	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (Xtreme H)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth		Ft.	890		
Surface	8 5/8 CSG 24"	Bottom of Surface		Ft.	878		
Plug		Plug Landed @	825	Ft.	Time On	1000	
Production		Pipe Landed @	878	Ft.	Plug Down	1300	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat	MIKE HINGREEN TYPE HL 125% EXCESS	700	SKS	
Poz. Mix	User ID ZMDL6			
Calcium Chloride	WBS/NO/CO 2043923.001	2.5	%	
Gal % Flo-Crete 1/4 # Per Sack	80062090			
Mileage Charge	G/L Acct.	180	Miles	
Fuel Surcharge		180	miles	
Additional Cement	Cement with 80ft 1"	200	SKS	
Mixing Rate	4 BPM	Pre-Flush	1200	1206
Disp. Rate	5 BPM	Mixing	1206	1209
Slurry Vol.	1.32 <sup>3</sup> Cu.Ft./Sk	Change Valves	1209	1250
Slurry Wt.	14.8 - 15.0 PPG	Displacement	1250	1300
Water/Cement	6.25 Gal/SK			
Water Temp.	65°F			
Total Slurry Vol.	211.5	BBLs Cement		
Landed Plug @	225	PSI/Final Lift @	225	PSI
Pre-Flush Wt	30	BBLs H <sub>2</sub> O	Tax Reference Code	Sub Total
Displace Wt	52.6	BBLs H <sub>2</sub> O	State CO 2.9%	Tax
Circulate	0	BBLs Cement		Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1201		Pump Truck		60			
1214/1218		Bulk Truck		60/60			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Jim, Adam, Jason, Tony

Received By

*[Signature]*  
Customer or His Agent