



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600358

Date <u>2/17/2012</u>	Well Owner <u>Kerr McGee</u>	Well No. <u>16-J6</u>	Lease <u>NORTHGLENN STATE</u>
County <u>WELD</u>	State <u>Colorado</u>		
Charge to <u>Kerr McGee Oil & Gas Onshore, LP</u>			
Address <u>1999 Broadway, Suite 3700 (XTREME#11)</u>			
City, State Zip <u>Denver, Colorado 80202</u>			
Type of Job	Depth	Fl. <u>1043</u>	
Surface <u>8 5/8 CSG 24</u>	Bottom of Surface	Fl. <u>1032</u>	
Plug	Plug Landed @ <u>990</u>	Fl. <u>0400</u>	
Production	Pipe Landed @ <u>1032</u>	Fl. <u>1030</u>	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat <u>TYPE III</u>	<u>650</u>	SKS		
Poz. Mix *				
Calcium Chloride	2.5	%		
Gel % Flo/Cete 1/4 # Per Sack				
Mileage Charge	<u>240</u>	Miles		
Fuel Surcharge	<u>240</u>	MILES		
Additional Cement	<u>40</u>	SKS		
Mixing Rate 4 BPM	Pre-Flush	<u>0931</u>	<u>0937</u>	
Disp. Rate 5 BPM	Mixing	<u>0937</u>	<u>1015</u>	
Slurry Vol. 1.32 ³ Cu.Ft./Sk	Change Valves	<u>1015</u>	<u>1019</u>	
Slurry Wt. 14.8 - 15.0 PPG	Displacement	<u>1019</u>	<u>1030</u>	
Water/Cement 6.25 Gal/SK				
Water Temp. <u>52</u>				
Total Slurry Vol. <u>162.2</u>	BBLS Cement			
Landed Plug @ <u>700</u>	PSI/Final Lift @ <u>550</u>	PSI		
Pre-Flush Wt <u>30</u>	BBLS H ₂ O	Tax Reference Code	Sub Total	
Displace Wt <u>62.9</u>	BBLS H ₂ O	State <u>CO 2.9%</u>	Tax	
Circulate <u>7</u>	BBLS Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<u>1201</u>		Pump Truck		<u>80</u>			
<u>1214/1217</u>		Bulk Truck		<u>80/80</u>			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By JEN ADAM/JASON

Received By B. Benjamin
Customer or His Agent