

# **WESTERN WELLSITE SERVICES, LLC**

**17509 County Road 14,  
Ft. Morgan, Colorado 80701  
(970)-867-9007 or (970)-867-8374 (Fax)**

## **Job Log**

Date: 6-7-12

Operator: Encana Oil and Gas  
Well name: Douglas Creek #39  
Rio Blanco County, Colorado  
Legal: Sec 5 – 3S – 101W  
AFE# 12165747

MIRU, NUBOP

Lay down production tubing – 60 jts, 1.9”

Rig up WL, TIH with guage ring to 1,620’

TIH with BP and set at 1,610’

Dump bail 35’ of cement on plug (5 sacks)

Pressure test casing to 500#

Perforate 267’

Attempt to establish a rate, casing pressured to 500#, no rate  
conclusion was annulus was cemented

RIH with tubing 326’

Pump 24 sxs of cement across the perfs

POH, WOC

RIH with wireline and tag at 245’

Per BLM rep, top fill casing and annulus with 21 sxs  
of cement.

Cut off wellhead

Top off cement with 1 sack.

Weld plate

RDMO

All cement is 15.8# class G neat

Cementing contractor: Magna Energy Services, LLC

Cementing contractor supervisor: Jeremy Rose

Operator supervisor: Brent Huckins, Cary Huckins

BLM supervisor: Steve Halcomb

Wireline contractor: Magna Energy Services, LLC