

**FORM  
5**Rev  
02/08**State of Colorado****Oil and Gas Conservation Commission**

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400305151

Date Received:

**DRILLING COMPLETION REPORT**

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 10071

4. Contact Name: Julie Webb

2. Name of Operator: BARRETT CORPORATION\* BILL

Phone: (303) 312-8714

3. Address: 1099 18TH ST STE 2300

Fax: (303) 291-0420

City: DENVER State: CO Zip: 80202

5. API Number 05-045-20944-00

6. County: GARFIELD

7. Well Name: EPPERLY

Well Number: 14B-23-692

8. Location: QtrQtr: NWSW Section: 23 Township: 6S Range: 92W Meridian: 6

Footage at surface: Distance: 2313 feet Direction: FSL Distance: 855 feet Direction: FWL

As Drilled Latitude: 39.511748 As Drilled Longitude: -107.640637

## GPS Data:

Data of Measurement: 11/30/2011 PDOP Reading: 6.0 GPS Instrument Operator's Name: T. Barnett

\*\* If directional footage at Top of Prod. Zone Dist.: 457 feet. Direction: FSL Dist.: 676 feet. Direction: FWL

Sec: 23 Twp: 6S Rng: 92W

\*\* If directional footage at Bottom Hole Dist.: 441 feet. Direction: FSL Dist.: 689 feet. Direction: FWL

Sec: 23 Twp: 6S Rng: 92W

9. Field Name: MAMM CREEK

10. Field Number: 52500

11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 11/26/2011 13. Date TD: 03/05/2012 14. Date Casing Set or D&amp;A: 03/05/2012

## 15. Well Classification:

☐ Dry ☐ Oil ☒ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 7965 TVD\*\* 7535 17 Plug Back Total Depth MD 7925 TVD\*\* 7539

18. Elevations GR 5853 KB 5875

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

## 19. List Electric Logs Run:

CBL, Mud, Temp, Triple Combo

## 20. Casing, Liner and Cement:

**CASING**

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	24	14	40	0	40		0	40	CALC
SURF	12+1/4	9+5/8	36	0	768	240	0	787	CALC
1ST	7+7/8	4+1/2	11.6	0	7,969	600	5,326	7,970	CBL

**STAGE/TOP OUT/REMEDIAL CEMENT**

Cement work date: \_\_\_\_\_

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

21. Formation log intervals and test zones:

**FORMATION LOG INTERVALS AND TEST ZONES**

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
WILLIAMS FORK	4,025		<input type="checkbox"/>	<input type="checkbox"/>	
ROLLINS	7,662		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

The 72 Hour Bradenhead Pressure Test was 0 psig. Conductor was cemented with grout. 8 3/4 hole size was used to drill from bottom of surface casing to 5868' then 7 7/8 hole size was used to drill to TD.  
As Drilled GPS is taken from conductor. Surface casing is set with air rig.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_

Print Name: Julie Webb

Title: Permit Analyst

Date:

Email: jwebb@billbarrettcorp.com

**Attachment Check List**

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
	CMT Summary *	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
400305178	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
400305176	LAS-MUD	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400305177	LAS-TEMPERATURE	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400305179	DIRECTIONAL DATA	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400306186	LAS-CEMENT BOND	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400306187	LAS-TRIPLE COMBINATION	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

**General Comments****User Group****Comment****Comment Date**

--	--	--

Total: 0 comment(s)