

Magna Energy Services, LLC
17509 County Road 14,
Ft. Morgan, Colorado 80701
(970)-867-9007 or (970)-867-8374 (Fax)

Job Log

Date: 6-29-12

Operator: EnCana Oil and Gas
API: 05-103-10002
Well name: Hells Hole 9123
Location: Rio Blanco, Colorado
Legals: Section 13, 2 South, 104 West
AFE #:

MIRU, TOH 92 joints of tubing
TIH to 2,828' and pump 71 sxs of cement, TOH and WOC
TIH and tag TOC at 2,472', Attempt to pressure test casing failed, wouldn't hold water
TIH to 2,425' pump 140 sxs of cement (700') Displace with 9 bbl.
TOH and reverse circulate out of hole, WOC
TIH and tag TOC at 1,759', Pressure test casing, Pressure did not hold
Pumped 122 sxs of cement, displaced with 6 bbl.
TOH and reverse circulated, WOC
TIH and tag TOC at 1,253', Pressure test casing, Pressure held for 15 min, TOH
RU wireline and perf at 279', RD wireline
Pumped 120 bbls down 7" to get circulation, no success
TIH to 279' and pumped 23 sacks of cement (110') Displace with 1 bbl. TOH and WOC
TIH to 305', no tag, and Pressure test failed
TOH to 279' Pump 28 sxs of cement (120') Displaced with ½ bbl. and TOH
TIH and tag at 139', Pressure tested, Pressure held, TOH
RU wireline and perf at 100', could not circulate with 128 bbls
TIH to 99' and pumped 36 sxs to surface, TOH and WOC
TIH and tag at 70'
Dig out and cut off wellhead, fill casing with 46 sxs of cement, WOC, weld on plate
RDMO

*** All cement is 15.8# Class "G" neat cement ***

Cementing contractor: Magna Energy Services, LLC
Cementing contractor supervisor: Jeremy Rose
Operator supervisor: Brent Huckins
BLM Representative: Steve Halcomb, Justin Wilson
Wireline contractor: Magna Energy Services, LLC