

FORM  
5Rev  
02/08

## State of Colorado

## Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400299466

Date Received:

06/25/2012

## DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 96850

4. Contact Name: Julie Lawson

2. Name of Operator: WPX ENERGY ROCKY MOUNTAIN LLC

Phone: (303) 260-4533

3. Address: 1001 17TH STREET - SUITE #1200

Fax: (303) 629-8268

City: DENVER State: CO Zip: 80202

5. API Number 05-103-11613-00

6. County: RIO BLANCO

7. Well Name: FEDERAL RGU

Well Number: 13-24-198

8. Location: QtrQtr: NWSW Section: 24 Township: 1S Range: 98W Meridian: 6

Footage at surface: Distance: 1751 feet Direction: FSL Distance: 1076 feet Direction: FWL

As Drilled Latitude: 39.946566 As Drilled Longitude: -108.347508

## GPS Data:

Date of Measurement: 08/29/2011 PDOP Reading: 2.6 GPS Instrument Operator's Name: J. Kirkpatrick

\*\* If directional footage at Top of Prod. Zone Dist.: 2359 feet. Direction: FSL Dist.: 626 feet. Direction: FWL

Sec: 24 Twp: 1S Rng: 98W

\*\* If directional footage at Bottom Hole Dist.: 2365 feet. Direction: FSL Dist.: 625 feet. Direction: FWL

Sec: 24 Twp: 1S Rng: 98W

9. Field Name: SULPHUR CREEK

10. Field Number: 80090

11. Federal, Indian or State Lease Number: COC060733

12. Spud Date: (when the 1st bit hit the dirt) 09/10/2011 13. Date TD: 10/25/2011 14. Date Casing Set or D&amp;A: 10/27/2011

## 15. Well Classification:

☐ Dry ☐ Oil ☒ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 12735 TVD\*\* 12694 17 Plug Back Total Depth MD 12705 TVD\*\* 12664

18. Elevations GR 6536 KB 6558

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

## 19. List Electric Logs Run:

SP/GR/HDIL/ZDL/CN/CBL/RPM &amp; MUD

## 20. Casing, Liner and Cement:

## CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	24	18	48	0	80	135	0	80	VISU
SURF	14+3/4	9+5/8	36	0	3,849	1,698	0	3,949	VISU
1ST	7+7/8	4+1/2	11.6	0	12,727	1,842	7,044	12,727	CBL

**STAGE/TOP OUT/REMEDIAL CEMENT**

Cement work date: \_\_\_\_\_

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

21. Formation log intervals and test zones:

**FORMATION LOG INTERVALS AND TEST ZONES**

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
WASATCH	5,795		<input type="checkbox"/>	<input type="checkbox"/>	
MESAVERDE	7,873		<input type="checkbox"/>	<input type="checkbox"/>	
CAMEO	10,956		<input type="checkbox"/>	<input type="checkbox"/>	
ROLLINS	11,525		<input type="checkbox"/>	<input type="checkbox"/>	
COZZETTE	11,663		<input type="checkbox"/>	<input type="checkbox"/>	
CORCORAN	11,881		<input type="checkbox"/>	<input type="checkbox"/>	
SEGO	12,272		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

Please note: the "as-drilled" GPS information provided is actual data of the existing well conductor location prior to the big rig spud date.

Surface Pressure = 0

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_

Print Name: Julie Lawson

Title: Permit Tech II

Date: 6/25/2012

Email: julie.lawson@wpenergy.com

**Attachment Check List**

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
400299483	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
400299482	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
400299466	FORM 5 SUBMITTED	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400299481	DIRECTIONAL DATA	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

**General Comments****User Group****Comment****Comment Date**

--	--	--

Total: 0 comment(s)