

**FORM
5**Rev
02/08**State of Colorado****Oil and Gas Conservation Commission**

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400307578

Date Received:

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☐ Final completion ☒ Preliminary completion

1. OGCC Operator Number: 96850

4. Contact Name: Angela Neifert-Kraiser

2. Name of Operator: WPX ENERGY ROCKY MOUNTAIN LLC

Phone: (303) 606-4398

3. Address: 1001 17TH STREET - SUITE #1200

Fax: (303) 629-8268

City: DENVER State: CO Zip: 80202

5. API Number 05-045-19700-00

6. County: GARFIELD

7. Well Name: Federal

Well Number: SP 341-14

8. Location: QtrQtr: SWNE Section: 14 Township: 7S Range: 95W Meridian: 6

Footage at surface: Distance: 2520 feet Direction: FNL Distance: 2592 feet Direction: FEL

As Drilled Latitude: 39.438131 As Drilled Longitude: -107.965034

GPS Data:

Date of Measurement: 06/16/2011 PDOP Reading: 1.7 GPS Instrument Operator's Name: Jack Kirkpatrick

** If directional footage at Top of Prod. Zone Dist.: feet. Direction: FNL Dist.: feet. Direction: FEL

Sec: 14 Twp: 7s Rng: 95w

** If directional footage at Bottom Hole Dist.: 474 feet. Direction: FNL Dist.: 693 feet. Direction: FEL

Sec: 14 Twp: 7s Rng: 95w

9. Field Name: PARACHUTE

10. Field Number: 67350

11. Federal, Indian or State Lease Number: COC05173

12. Spud Date: (when the 1st bit hit the dirt) 12/17/2011 13. Date TD: 12/28/2011 14. Date Casing Set or D&A: 12/29/2011

15. Well Classification:

☐ Dry ☐ Oil ☒ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 9725 TVD** 9102 17 Plug Back Total Depth MD TVD**

18. Elevations GR 7637 KB 7661

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

CBL, Mud, and Reservoir Performance Monitor (RPM)
Deferred completion until end of 2013

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	26	18	48	0	80	39	0	80	VISU
SURF	13+1/2	9+5/8	32.3	0	2,452	620	0	2,452	VISU
1ST	7+7/8	4+1/2	11.6	0	9,703	975		9,703	CBL

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
WASATCH G	4,022		<input type="checkbox"/>	<input type="checkbox"/>	
MESAVERDE	6,378		<input type="checkbox"/>	<input type="checkbox"/>	
CAMEO	8,632		<input type="checkbox"/>	<input type="checkbox"/>	
ROLLINS	9,633		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

Please note: the "as-drilled" GPS information provided is actual data of the existing well conductor location prior to the big rig spud date.

*All flowback water entries are total estimates based on comingled volumes.
Deferred completion until end of 2013

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Angela Neifert-Kraiser

Title: Regulatory Specialist

Date:

Email: Angela.Neifert-Kraiser@WPXEnergy.com

Attachment Check List

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
400307586	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
400307587	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
400307585	DIRECTIONAL DATA	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400307589	WELLBORE DIAGRAM	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

General Comments

User Group	Comment	Comment Date

Total: 0 comment(s)