

**WPX ENERGY ROCKY MOUNTAIN, LLC**

**Jolley KP 11-17**

**Kokopelli Field**

**SHL 186' FSL 2300' FWL (SE/4 SW/4) BHL 160' FNL 663' FWL (NW/4 NW/4 SEC. 17 T6S-R91W)**

**Section 8-T6S-R91W 6th PM**

**Garfield County, Colorado**

**Formation Tops**

(Measured Depths)

**Mesaverde @ 3856'**

**Cameo @ 7340'**

**Rollins @ 7582'**

**PBTD @**

**TMD @ 7761'**

**TVD @ 7388'**

**Conductor 24" Hole 16" casing/liner 40' w/15sks cmt**

**Cmt @ Surface - (Cmt circ to surf during cmt job)**

**9 5/8" 32.3# ppf Csg. Set @1348'**

**In 12 1/4" Hole W/370 Sks. Cmt**

**4-1/2", 11.6 ppf. Csg. Set @7753' W/1125 sks Cmt**