



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600562

Date	6/28/12	Well Owner	Kerr McGee	Well No.	27-2	Lease	Cambrecht
County	Weld	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (Xtreme II)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth		FL	956		
Surface	8 5/8" CSG 24"	Bottom of Surface		FL	946		
Plug		Plug Landed @	901	FL	Time On	0730	
Production		Pipe Landed @	946	FL	Plug Down	0930	
Description		Qty.	Mess.	Unit Price	Amount		
Set Up Charge		1					
Cement Neat	TYPE III	600	SKS				
Poz. Mix	Duaine Bell						
Calcium Chloride		2.5	%				
Gel %	Flow 1/4" 2053815						
Mileage Charge	WBS/WO/CC 2053815	180	Miles				
Fuel Surcharge	G/L Acct. 80012090	180	miles				
Additional Cement			SKS				
Mixing Rate	4 BPM	Pre-Flush	0835	0841			
Disp. Rate	5 BPM	Mixing	0841	0916			
Slurry Vol.	1.32 ³ Cu.FL/Sk	Change Valves	0916	0919			
Slurry Wt.	14.8 - 15.0 PPG	Displacement	0919	0930			
Water/Cement	6.25 Gal/SK						
Water Temp.	70°F						
Total Slurry Vol.	141.0	BBLS Cement					
Landed Plug @	425	PSI/Final Lift @	450	PSI			
Pre-Flush Wt	20	BBLS H ₂ O	Tax Reference Code	Sub Total			
Displace Wt	57.3	BBLS H ₂ O	State CO 2.9%	Tax			
Circulate	4	BBLS Cement		Total			
Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1201		Pump Truck		60			
1217/1218		Bulk Truck		60/60			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Jim, Adam, Steve, Malco

Received By [Signature]

Customer or His Agent