

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400309867

Date Received:

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER ☐
SINGLE ZONE ☐ MULTIPLE ☐ COMMINGLE ☐

Refiling ☐

Sidetrack ☐

PluggingBond SuretyID

20030110

3. Name of Operator: WHITING OIL AND GAS CORPORATION

4. COGCC Operator Number: 96155

5. Address: 1700 BROADWAY STE 2300

City: DENVER State: CO Zip: 80290

6. Contact Name: Larry Brown Phone: (307)237-9310 Fax: ()

Email: ld_brown@bresnan.net

7. Well Name: Razor Well Number: 14-1143H

8. Unit Name (if appl): Unit Number:

9. Proposed Total Measured Depth: 12540

WELL LOCATION INFORMATION

10. QtrQtr: SESE Sec: 14 Twp: 10N Rng: 58W Meridian: 6

Latitude: 40.832447 Longitude: -103.825372

Footage at Surface: 332 feet FNL/FSL FSL 660 feet FEL/FWL FEL

11. Field Name: Field Number:

12. Ground Elevation: 4932 13. County: WELD

14. GPS Data:

Date of Measurement: 05/23/2012 PDOP Reading: 1.0 Instrument Operator's Name: Jerromy Harris

15. If well is ☐ Directional ☒ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 862 FSL 664 FEL FEL Bottom Hole: FNL/FSL 1980 FSL 660 FEL FEL
Sec: 14 Twp: 10n Rng: 58W Sec: 11 Twp: 10N Rng: 58W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 309 ft

18. Distance to nearest property line: 332 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 5280 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Niobrara	NBRR	535-150	960	

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #:

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

All of Section 14, s/2 Section 11 T10N R58W

25. Distance to Nearest Mineral Lease Line: 332

26. Total Acres in Lease: 640

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☐ Land Spreading ☒ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	26	20		0	80		80	0
SURF	13+1/2	9+5/8	36	0	1,650	819	1,650	0
1ST	8+3/4	7	29	0	6,110	427	6,110	0
2ND	6	4+1/2	11.6	5292	12,540			

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments _____

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Larry D. Brown

Title: Agent Date: _____ Email: ld_brown@bresnan.net

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

API NUMBER

05

Permit Number: _____ Expiration Date: _____

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Attachment Check List

Att Doc Num	Name
400309905	PLAT
400309907	TOPO MAP
400309909	DRILLING PLAN
400309910	DIRECTIONAL DATA
400309911	DIRECTIONAL DATA

Total Attach: 5 Files

General Comments

User Group	Comment	Comment Date

Total: 0 comment(s)

BMP

Type	Comment
Storm Water/Erosion Control	Stormwater management plans (SWMP) are in place to address construction, drilling and operations associated with oil and gas development throughout the State of Colorado. BMPs will be constructed as necessary to prevent stormwater from leaving the construction site. BMPs used will vary according to the location, and will remain until the pad is reclaimed.
Material Handling and Spill Prevention	<p>Spill Prevention Control and Countermeasures (SPCC) plans are in place to address any possible spill associated with oil and gas operations throughout the State of Colorado.</p> <ul style="list-style-type: none">• Materials and fluids will be stored in a neat and orderly fashion.• Waste will be collected regularly and disposed of at an offsite facility.• Prompt cleanup is required of spills to minimize waste materials entering the stormwater runoff.• Drip pans will be used during fueling and maintenance to contain spills or leaks.• Cleanup of trash and discarded material will be done at the end of the work day.• Cleanup will consist of monitoring the road, location and any other work areas.• Material to be cleaned up includes trash, scrap, and contaminated soil.

Total: 2 comment(s)