

FORM
5
Rev
02/08

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:
400311034

Date Received:

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type Final completion Preliminary completion

1. OGCC Operator Number: 100322
2. Name of Operator: NOBLE ENERGY INC
3. Address: 1625 BROADWAY STE 2200
City: DENVER State: CO Zip: 80202
4. Contact Name: EILEEN ROBERTS
Phone: (303) 2284330
Fax: (303) 2284286

5. API Number 05-123-33440-00
6. County: WELD
7. Well Name: SATER Well Number: C26-69HN
8. Location: QtrQtr: SESE Section: 23 Township: 4N Range: 64W Meridian: 6
Footage at surface: Distance: 327 feet Direction: FSL Distance: 190 feet Direction: FEL
As Drilled Latitude: 40.291610 As Drilled Longitude: -104.509180

GPS Data:

Data of Measurement: 11/11/2011 PDOP Reading: 4.4 GPS Instrument Operator's Name: Paul Tappy

** If directional footage at Top of Prod. Zone Dist.: 157 feet. Direction: FSL Dist.: 485 feet. Direction: FEL

Sec: 22 Twp: 4N Rng: 64W

** If directional footage at Bottom Hole Dist.: 26 feet. Direction: FSL Dist.: 410 feet. Direction: FEL

Sec: 22 Twp: 4N Rng: 64W

9. Field Name: WATTENBERG 10. Field Number: 90750

11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 09/12/2011 13. Date TD: 09/15/2011 14. Date Casing Set or D&A: 09/17/2011

15. Well Classification:

Dry Oil Gas/Coalbed Disposal Stratigraphic Enhanced Recovery Storage Observation

16. Total Depth MD 11536 TVD** 6687 17 Plug Back Total Depth MD 11513 TVD** 6664

18. Elevations GR 4674 KB 4698

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

GRL/CCL/CBL/VDL.

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	18+1/2	16+0/0	84.00	24	125	172	0	125	
SURF	13+3/4	9+5/8	36.00	26	670	361	0	680	
1ST	8+3/4	7+0/0	26.00	24	7,037	570	1,500	7,046	CBL
1ST LINER	6+1/8	4+1/2	11.60	5932	10,521	0	0	10,521	

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
SUSSEX	4,227		<input type="checkbox"/>	<input type="checkbox"/>	
SHANNON	4,829		<input type="checkbox"/>	<input type="checkbox"/>	
NIOBRARA	6,541		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Eileen Roberts

Title: Regulatory Specialist Date: _____ Email: eroberts@nobleenergyinc.com

Attachment Check List

Att Doc Num	Document Name	attached ?	
Attachment Checklist			
400311347	CMT Summary *	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
400311348	Directional Survey **	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Logs	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Other	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
Other Attachments			
400311344	LAS-CEMENT BOND	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400311361	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>

General Comments

User Group	Comment	Comment Date

Total: 0 comment(s)