



## CEMENT JOB REPORT

Page 4

# CEMENT JOB REPORT



## Shoe Test (Update Original Treatment Report for Primary Job)

Depth Drilled out of Shoe: 0 FT Target EMW: 0 LBS/GAL Actual EMW: 0 LBS/GAL  
 Number of Times Tests Conducted: 0 Mud Weight When Test was Conducted: LBS/GAL

Problems Before Job (I.E. Running Casing, Circulating Well, ETC)  
 N/A

Problems During Job (I.E. Lost Returns, Equipment Failure, Bulk Delivery, Foaming, ETC)  
 N/A

Problems After Job (I.E. Gas at Surface, Float Equipment Failed, ETC)  
 N/A

EXPLANATION: TROUBLE SETTING TOOL, RUNNING CSG, ETC. PRIOR TO CEMENTING: NONE

PRESSURE/RATE DETAIL						EXPLANATION	
TIME HR:MIN.	PRESSURE - PSI		RATE BPM	BBL FLUID PUMPED	FLUID TYPE	SAFETY MEETING: BJ CREW <input checked="" type="checkbox"/> CO. REP. <input checked="" type="checkbox"/>	
	PIPE	ANNULUS				TEST LINES	4000 PSI
						CIRCULATING WELL - RIG	<input checked="" type="checkbox"/> BJ
14:40	0	0	0	0	N/A	PRE RIG UP SAFETY MEETING	
16:30	0	0	0	0	N/A	JOB SAFETY MEETING	
16:43	4010	0	3	3	H2O	PRESSURE TEST C992	
16:45	491	0	6	10	H2O	PREFLUSHW/ FRESH WATER	
16:50	426	0	5	20	H2O	PREFLUSH W/ ULTRA FLUSH	
16:54	354	0	5	10	H2O	PREFLUHW/ FRESH WATER	
16:58	656	0	7.4	271	CEMENT	BATCH UP AND PUMP 820 SKS OF PLC + 0.25% R-3 + 0.4% FL-52 + % BENTONITE + 89.4% FRESH WATER @ 12.5 PPG.	
17:39	291	0	6	50	CEMENT	BATCH UP AND PUMP 150 SKS POZ G + 0.4% FL-52 + 3% BENTONITE + 0.1% SODIUM METASILICATE + 20% SILICA FLOUR + 82.4% FRESH WATER @ 13.5 PPG.	
17:50	0	0	0	0	N/A	WASH PUMPS AND LINE, DROP PLUG	
17:55	656	0	9.6	75	H2O	DISPLACEMENT W/ CT-3C	
18:05	1691	0	7.2	15	H2O	DROP RATE DUE TO PRESSURE DIFFERENTIAL	
18:07	1707	0	4.8	10	H2O	DROP RATE DUE TO PRESSURE DIFFERENTIAL	
18:09	1717	0	2.4	15	H2O	DROP RATE DUE TO PRESSURE DIFFERENTIAL	
18:12	2509	0	2.4	0	N/A	BUMP PLUG	
18:15	0	0	0	0	N/A	PLUG DOWN	
18:17	0	0	0	0	N/A	PRE RIG DOWN SAFETY MEETING	
BUMPED PLUG	PSI TO BUMP PLUG	TEST FLOAT EQUIP.	BBL CMT RETURNS/ REVERSED	TOTAL BBL PUMPED	PSI LEFT ON CSG	SPOT TOP OUT CEMENT	Service Supervisor Signature:
<input checked="" type="checkbox"/> Y <input type="checkbox"/> N	2509	<input checked="" type="checkbox"/> Y <input type="checkbox"/> N	15	478	0	<input checked="" type="checkbox"/> Y <input type="checkbox"/> N	