

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400304690

Date Received:

07/11/2012

PluggingBond SuretyID

20030107

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refiling ☒

Sidetrack ☐

3. Name of Operator: WPX ENERGY ROCKY MOUNTAIN LLC

4. COGCC Operator Number: 96850

5. Address: 1001 17TH STREET - SUITE #1200

City: DENVER State: CO Zip: 80202

6. Contact Name: Howard Harris Phone: (303)606-4086 Fax: (303)629-8268

Email: howard.harris@williams.com

7. Well Name: Savage Well Number: PA 314-4

8. Unit Name (if appl): Unit Number:

9. Proposed Total Measured Depth: 7061

WELL LOCATION INFORMATION

10. QtrQtr: NESW Sec: 4 Twp: 7S Rng: 95W Meridian: 6

Latitude: 39.463409 Longitude: -108.006813

Footage at Surface: 1481 feet FNL/FSL 1462 feet FEL/FWL
FSL FWL

11. Field Name: Parachute Field Number: 67350

12. Ground Elevation: 5586 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 06/11/2008 PDOP Reading: 1.4 Instrument Operator's Name: J. Kirkpatrick

15. If well is ☒ Directional ☐ Horizontal (highly deviated) submit deviated drilling plan.

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL
809 FSL 622 FWL 809 FSL 622 FWL
Sec: 4 Twp: 7S Rng: 95W Sec: 4 Twp: 7S Rng: 95W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 1183 ft

18. Distance to nearest property line: 1072 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 305 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Williams Fork	WMFK	440-35	320	S/2

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No: ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

T7S-R95W: Sec. 4: SW/4SE/4, SW/4

25. Distance to Nearest Mineral Lease Line: 622 ft

26. Total Acres in Lease: 200

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☐ Offsite ☒ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Re-Use, Evap & Backfill

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	24	18	48	0	45	25	45	0
SURF	13+1/2	9+5/8	32.3	0	909	317	909	0
1ST	8+3/4	4+1/2	11.6	0	7,061	563	7,061	3,600

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments Top of cement for production casing will be approx 200 feet above the top of Mesaverde. Closed mud system will be used. Surface Use Agreement attached to form 2A. CA# Co07320Associated From 2A Doc# 400089643 for location is approved. No changes are being made on this form 2 except change of hole size on production casing from 7 7/8" to 8 3/4".

34. Location ID: 334813

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☐ Yes ☒ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Howard Harris

Title: Sr. Regulatory Specialist Date: 7/11/2012 Email: howard.harris@williams.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved:  Director of COGCC Date: 8/3/2012

API NUMBER

05 045 20090 00

Permit Number: _____ Expiration Date: 8/2/2014

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.

2) GARFIELD COUNTY RULISON FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE

3) CEMENT ON PRODUCTION CASING MUST BE A MINIMUM OF 200' ABOVE THE TOP OF THE MESA VERDE FORMATION (OR 200' ABOVE THE OHIO CREEK FORMATION IF PRESENT). CEMENT TOP VERIFICATION BY CBL IS REQUIRED. THIS REQUIREMENT SHALL SUPERSEDE THE TOP OF CEMENT REQUIREMENTS IN THE NEW MAMM CREEK FIELD NOTICE TO OPERATORS.

4) THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1 MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 275 FEET DEEP.

Attachment Check List

Att Doc Num	Name
400304690	FORM 2 SUBMITTED

Total Attach: 1 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Per oper. corrected lease description, changed #36 to "NO". 2A #400089643 expires 10/21/2013. Loc. has 6 producing wells. No LGD or public comments. Final Review--passed.	3/2/2012 7:59:57 AM
LGD	Passed DB	7/12/2012 12:19:27 PM

Total: 2 comment(s)

BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)