

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400299590

Date Received:

06/29/2012

PluggingBond SuretyID

20030107

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refiling ☐

Sidetrack ☐

3. Name of Operator: WPX ENERGY ROCKY MOUNTAIN LLC

4. COGCC Operator Number: 96850

5. Address: 1001 17TH STREET - SUITE #1200

City: DENVER State: CO Zip: 80202

6. Contact Name: Howard Harris Phone: (303)606-4086 Fax: (303)629-8268

Email: howard.harris@williams.com

7. Well Name: Duggan Well Number: RWF 414-29

8. Unit Name (if appl): Unit Number:

9. Proposed Total Measured Depth: 7917

WELL LOCATION INFORMATION

10. QtrQtr: Lot 5 Sec: 29 Twp: 6S Rng: 94W Meridian: 6

Latitude: 39.490084 Longitude: -107.918630

Footage at Surface: 534 feet FNL/FSL 590 feet FEL/FWL
FSL FWL

11. Field Name: Rulison Field Number: 75400

12. Ground Elevation: 5415 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 05/30/2008 PDOP Reading: 1.8 Instrument Operator's Name: J. Kirkpatrick

15. If well is ☒ Directional ☐ Horizontal (highly deviated) submit deviated drilling plan.

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL
876 FSL 665 FWL 876 FSL 665 FWL
Sec: 29 Twp: 6S Rng: 94W Sec: 29 Twp: 6S Rng: 94W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 470 ft

18. Distance to nearest property line: 284 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 301 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Williams Fork	WMFK	479-14	320	S/2

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☒ No

23b. If 23 is No: ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

See Attached

25. Distance to Nearest Mineral Lease Line: 457 ft

26. Total Acres in Lease: 180

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☐ Offsite ☒ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Re-Use, Evap & Backfill

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	24	18	48	0	40	50	40	0
SURF	13+1/2	9+5/8	32.3	0	1,102	352	1,102	0
1ST	8+3/4	4+1/2	11.6	0	7,917	924	7,917	4,095

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments Top of production casing will be approx 200 feet above the top of Mesaverde. Fee minerals and Fee surface. We are permitting 13 wells at this time to be drilled from this pad. Closed loop mud system will be used. Surface Use Agreement attached to form 2A.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Howard Harris

Title: Sr. Regulatory Specialist Date: 6/29/2012 Email: howard.harris@williams.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved:  Director of COGCC Date: 8/3/2012

API NUMBER

05 045 21656 00

Permit Number: _____ Expiration Date: 8/2/2014

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 290 FEET DEEP.

TOP OF CEMENT ON PRODUCTION CASING MUST BE AT LEAST 200' ABOVE THE MESA VERDE.

ADHERENCE(S) TO THE FOLLOWING NOTICE TO OPERATORS APPLIES:

NW AREA NOTIFICATION PROCEDURES
GARFIELD COUNTY
GARFIELD & MESA COUNTY BRHTA

Attachment Check List

Att Doc Num	Name
400299590	FORM 2 SUBMITTED
400299597	DIRECTIONAL DATA
400299598	OIL & GAS LEASE
400299599	DEVIATED DRILLING PLAN
400299600	WELL LOCATION PLAT

Total Attach: 5 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	No LGD or public comments. Final Review--passed.	3/3/2012 3:06:05 PM
Permit	Deleted "fee pooled" from unit designation.	7/27/2012 10:19:49 AM
LGD	Passed DB	7/2/2012 3:31:53 PM
Permit	This form has passed completeness. SUA is attached to form 2A.	7/2/2012 11:44:58 AM
Permit	SUA not attached. Operator does not want to attach SUA until he hears from Jane.	6/29/2012 11:40:53 AM

Total: 5 comment(s)

BMP

<u>Type</u>	<u>Comment</u>
Drilling/Completion Operations	<ul style="list-style-type: none">• Use centralized hydraulic fracturing operations.• Install and maintain adequate measures to exclude all types of wildlife (e.g., big game, birds, and small rodents) from all fluid pits (e.g., fencing, netting, and other appropriate exclusion measures).• Conduct well completions with drilling operations to limit the number of rig moves and traffic.
Final Reclamation	<ul style="list-style-type: none">• Remove well pad and road surface materials that are incompatible with post-production land use and re-vegetation requirements• Use only certified weed-free native seed in seed mixes, except for non-native plants that benefit wildlife• Williams will use certified, weed free grass hay, straw, hay or other mulch materials used for the reseeding and reclamation of disturbed areas.• Install exclusionary devices to prevent bird and other wildlife access to equipment stacks, vents and openings.• Reduce visits to well-sites through remote monitoring (i.e. SCADA) and the use of multi-function contractors.• Avoid dust suppression activities within 300 feet of the ordinary high water mark of any reservoir, lake, wetland, or natural perennial or seasonally flowing stream or river where possible.
Planning	<ul style="list-style-type: none">• Share/consolidate corridors for pipeline ROWs to the maximum extent possible.• Maximize the utility of surface facilities by developing multiple wells from a single pad (directional drilling), and by co-locating multipurpose facilities (for example, well pads and compressors) to avoid unnecessary habitat fragmentation and disturbance of additional geographic areas.• Minimize newly planned activities and operations within 300 feet of the ordinary high water mark of any reservoir, lake, wetland, or natural perennial or seasonally flowing stream or river.• Avoid new surface disturbance and placing new facilities in key wildlife habitats in consultation with CPW.• Minimize the number, length, and footprint of oil and gas development roads• Use existing roads where possible• Combine and share roads to minimize habitat fragmentation• Place roads to avoid obstructions to migratory routes for wildlife, and to avoid displacement of wildlife from public to private lands.• Maximize the use of directional drilling to minimize habitat loss/fragmentation• Maximize use of remote completion/frac operations to minimize traffic• Maximize use of remote telemetry for well monitoring to minimize traffic• Restrict oil and gas activities as practical during critical seasonal periods

Total: 3 comment(s)