

FORM
5A

Rev
06/12

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400312965

Date Received:

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 96850
2. Name of Operator: WPX ENERGY ROCKY MOUNTAIN LLC
3. Address: 1001 17TH STREET - SUITE #1200
City: DENVER State: CO Zip: 80202
4. Contact Name: Matt Barber
Phone: (303) 606-4385
Fax: (303) 629-8268

5. API Number 05-045-20989-00
6. County: GARFIELD
7. Well Name: Jolley
Well Number: KP 431-17
8. Location: QtrQtr: SESW Section: 8 Township: 6S Range: 91W Meridian: 6
9. Field Name: KOKOPELLI Field Code: 47525

Completed Interval

FORMATION: WILLIAMS FORK - CAMEO Status: PRODUCING Treatment Type: FRACTURE STIMULATION

Treatment Date: 04/05/2012 End Date: 04/08/2012 Date of First Production this formation: 04/10/2012

Perforations Top: 5525 Bottom: 7327 No. Holes: 143 Hole size: 0.35

Provide a brief summary of the formation treatment: Open Hole: ☐

2650 gals 7.5% HCL; 69,018# 100-MESH Sand; 865,458# 30/50 Sand; 25,186 Bbls Slickwater

This formation is commingled with another formation: ☐ Yes ☒ No

Total fluid used in treatment (bbl): 25249

Max pressure during treatment (psi):

Total gas used in treatment (mcf):

Fluid density at initial fracture (lbs/gal): 8.43

Type of gas used in treatment:

Max frac gradient (psi/ft): 0.61

Total acid used in treatment (bbl): 63

Number of staged intervals: 6

Recycled water used in treatment (bbl): 25186

Flowback volume recovered (bbl):

Fresh water used in treatment (bbl):

Disposition method for flowback: RECYCLE

Total proppant used (lbs): 934476

Rule 805 green completion techniques were utilized: ☒

Reason why green completion not utilized:

Fracture stimulations must be reported on FracFocus.org

Test Information:

Date: 04/30/2012 Hours: 24 Bbl oil: Mcf Gas: 929 Bbl H2O:

Calculated 24 hour rate: Bbl oil: Mcf Gas: 929 Bbl H2O: GOR:

Test Method: Flowing Casing PSI: 992 Tubing PSI: 647 Choke Size: 24/64

Gas Disposition: SOLD Gas Type: DRY Btu Gas: 1201 API Gravity Oil:

Tubing Size: 2 + 3/8 Tubing Setting Depth: 6813 Tbg setting date: 04/10/2012 Packer Depth:

Reason for Non-Production:

Date formation Abandoned: Squeeze: ☐ Yes ☐ No If yes, number of sacks cmt

** Bridge Plug Depth: ** Sacks cement on top: ** Wireline and Cement Job Summary must be attached.

Comment:

*All flowback water entries are total estimates based on comingled volumes.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Matt Barber

Title: Sr. Regulatory Specialist Date: _____ Email matt.barber@wpenergy.com
:

Attachment Check List

Att Doc Num	Name
400313133	WELLBORE DIAGRAM

Total Attach: 1 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)