

Williams Production RMT Co.

Jolley KP 431-17

Kokopelli Field

SHL 190' FSL 2353' FWL (SE/4 SW/4) BHL 683' FNL 1984' FEL (NW/4 NE/4 Sec. 17-T6S-R91W)

Section 8-T6S-R91W 6th PM

Garfield County, Colorado

Formation Tops
(Measured Depths)

Mesaverde @ 3680'

Cameo @ 7072'

Rollins @ 7355'

PBTD @ 7544'

TMD @ 7600'

TVD @ 7377'

Conductor 26" Hole 16" casing/liner 67' W/25 sks cmt

Cmt @ Surface - (Cmt circ to surf during cmt job)

9 5/8" 32.3# ppf Csg. Set @ 1299'

In 12 1/4" Hole W/350 Sks. Cmt

Top Of Cement 3284'

5525-5730' Mesaverde

5784-5973' Mesaverde

6095-6402' Mesaverde

6486-6729' Mesaverde

6781-6986' Mesaverde

7077-7327' Cameo

4-1/2", 11.6 ppf. Csg. Set @ 7578' W/1220 sks Cmt