

FORM
2
Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400269581

Date Received:

05/07/2012

PluggingBond SuretyID

20080107

APPLICATION FOR PERMIT TO:

1. Drill, Deepen, Re-enter, Recomplete and Operate

2. TYPE OF WELL

OIL GAS COALBED OTHER pilot
SINGLE ZONE MULTIPLE COMMINGLE

Refiling
Sidetrack

3. Name of Operator: QUICKSILVER RESOURCES INC

4. COGCC Operator Number: 10255

5. Address: 801 CHERRY ST - #3700 UNIT 19

City: FT WORTH State: TX Zip: 76102

6. Contact Name: PAMELA OSBURN Phone: (817)665-4918 Fax: (817)665-5009

Email: posburn@qrinc.com

7. Well Name: WELKER Well Number: 21-12

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 8300

WELL LOCATION INFORMATION

10. QtrQtr: NE NW Sec: 12 Twp: 6N Rng: 92W Meridian: 6

Latitude: 40.488903 Longitude: -107.670294

Footage at Surface: 1320 feet FNL 1980 feet FWL

11. Field Name: WILDCAT Field Number: 99999

12. Ground Elevation: 6437 13. County: MOFFAT

14. GPS Data:

Date of Measurement: 02/15/2012 PDOP Reading: 1.3 Instrument Operator's Name: UINTAH ENGINEERING

15. If well is Directional Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL

Sec: Twp: Rng: Sec: Twp: Rng:

16. Is location in a high density area? (Rule 603b)? Yes No

17. Distance to the nearest building, public road, above ground utility or railroad: 1474 ft

18. Distance to nearest property line: 659 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 3000 ft

LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR			

21. Mineral Ownership: Fee State Federal Indian Lease #: _____

22. Surface Ownership: Fee State Federal Indian

23. Is the Surface Owner also the Mineral Owner? Yes No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? Yes No

23b. If 23 is No: Surface Owners Agreement Attached or \$25,000 Blanket Surface Bond \$2,000 Surface Bond \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

E/2W/2 Sec. 12:T6n-R92W, Moffat Co. and other lands.

25. Distance to Nearest Mineral Lease Line: 600 ft 26. Total Acres in Lease: 950

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? Yes No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? Yes No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? Yes No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? Yes No

31. Mud disposal: Offsite Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: Land Farming Land Spreading Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	20	16		0	40			
SURF	12+1/4	9+5/8	36	0	1,200	395	1,200	0
1ST	8+3/4	7	26	0	6,158	520	6,158	0
2ND	6+1/8	4+1/2	13.5	0	7,408	155	7,408	5,158

32. BOP Equipment Type: Annular Preventer Double Ram Rotating Head None

33. Comments Fee leasehold pooled.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? Yes No

36. Is this application part of submitted Oil and Gas Location Assessment ? Yes No


I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: PAMELA S. OSBURN

Title: SR. REGULATORY ANALYST Date: 5/7/2012 Email: posburn@qrinc.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved:  Director of COGCC Date: 8/7/2012

API NUMBER **05 081 07741 00** Permit Number: _____ Expiration Date: 8/6/2014

CONDITIONS OF APPROVAL, IF ANY: _____

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Before placing oil/salt based muds in a pit, operator must file and receive prior approval of a Pit Permit, Form 15. COGCC regulations regarding pit permits can be found in Rule 903.a.(3). PIT PERMITTING/REPORTING REQUIREMENTS.

- 1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.
- 2) PROVIDE CEMENT COVERAGE FROM THE INTERMEDIATE CASING SHOE TO A MINIMUM OF 200' ABOVE TOP OF GAS [OR OTHER SHALLOWEST-KNOWN PRODUCING HORIZON]. VERIFY CEMENT WITH A CEMENT BOND LOG.
- 3) PRODUCTION CASING CEMENT TOP VERIFICATION BY CBL REQUIRED.
- 4) THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1 MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 620 FEET DEEP.

Attachment Check List

Att Doc Num	Name
400269581	FORM 2 SUBMITTED
400269680	SURFACE AGRMT/SURETY
400269681	WELL LOCATION PLAT

Total Attach: 3 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Changed #36 to "YES", added related 2A, per oper.'s instructions changed lease description and acreage. No LGD or public comments. Final Review--passed.	6/15/2012 10:45:51 AM
Permit	Operator corrected 2b, 17, 18, 19, 25, and deleted O&G leases. This form has passed completeness.	5/11/2012 6:22:35 AM
Permit	Returned to draft at operators request.	5/8/2012 12:17:04 PM
Permit	Returned to draft. Missing 2b, 17, 18, 19, 25, and O&G leases are for a different location.	5/8/2012 7:37:55 AM

Total: 4 comment(s)

BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)