



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

200365

(P.O.# 201548)

Date <u>2/18/12</u>	Well Owner <u>Synergy Resources</u>	Well No. <u>13-8D</u>	Lease <u>Hilfer</u>
County <u>weld</u>	State <u>Colorado</u>	Field	
Charge to <u>ENSIGN US Drilling</u>	Charge Code		
Address <u>P.O. Box 17805 (ENSIGN-33)</u>	For Office Use Only		
City, State <u>Denver, Colorado 80217</u>			
Pump Truck No. <u>1208</u>	Code	Bulk Truck No. <u>1214</u>	Code
Type of Job	Depth	Ft. <u>581</u>	To
Surface <u>8 5/8" CSG-24 #</u>	Bottom of Surface	Ft. <u>571</u>	To
Plug	Plug Landed @ <u>532</u>	Ft.	Time On <u>1645</u>
Production	Pipe Landed @ <u>571</u>	Ft.	Time Off <u>Plug Down 1915</u>

Reference No.	Description	Qty.	Meas.	Unit Price	Amount	
	Pump Truck Charge					
	Cement Neat ✓	400	SKS			
	Poz. Mix					
	Calcium Chloride	3%				
	Gel % Flo-Cele $\frac{1}{4}$ #Per Sack					
	Handling Charge					
	Hauling Charge					
	Additional Cement					
8 5/8"	Centralizers	3		70.00		
	Cement Basket	1				
	Guide Shoe	1				
	Baffle Plate	1				
	Box thread lock	1				
Mix Rate 4	BPM	Slurry vol- 1.18 FT ³ /SK- water Temp 44°F				
Disp Rate 4	BPM	Slurry WT 15.2 PPG				
Plug landed @ 600 PSI		Total Slurry vol- 84 BBL Cement				
Remarks	Pre-Flush w/ 20 BBL H ² O		Tax Reference Code		Sub Total	
Displace w/ 33.8 BBL H ² O			State CO 2.9 %		Tax	
Circulate 5 BBL Cement			Disc.		Total	
Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other
1208		Pump Truck		30		
1214		Bulk Truck		30		

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Justin, Steve, Chris & Ewan

Received By Ron Black

Customer or His Agent