

Bayswater – Apollo 2012-2013 Drilling Program

Well Name: Bayswater Booth 3-26

Surface Location: 272 FNL 2535 FEL, NWNE 26 T7N R65W, Weld County, Colorado

Estimated BHL: 677 FNL 2003 FWL, NE NW 26 T7N R65W

Estimated Elevation: GR 4893, KB 4909

Estimated Surface Casing: 690

Estimated TD: 7360

<u>Formation</u>	<u>Depth (KB)/ (Struct)</u>	<u>Estimated Measured Depth</u>
Larimer (Parkman)	3811/1098	3889
Terry (Sussex)	4566/343	4666
Hygiene (Shannon)	5116/-207	5217
Niobrara	6916/-2007	7017
Fort Hays	7168/-2259	7269
Codell	7212/-2303	7313
Greenhorn	7264/-2355	7365
Graneros	7346/-2437	7447
TD	7360	7461

Primary Objectives: Niobrara A, B, C, Codell

Secondary Objectives: Greenhorn, Larimer (Parkman)

Logging Coverage: TD to Surface (GR/Ind)
TD to 3500' (CNL/FDC)

Cement Coverage: TD to 3500'