

## Bayswater – Apollo 2012-2013 Drilling Program

Well Name: Bayswater Booth 21-26

Surface Location: 545 FNL 2347 FEL, NWNE 26 T7N R65W, Weld County, Colorado

Estimated BHL: 1354 FNL 2554 FEL, C of West Line of NE 26 T7N R65W

Estimated Elevation: GR 4894, KB 4910

Estimated Surface Casing: 690

Estimated TD: 7350

<u>Formation</u>	<u>Depth (KB)/ (Struct)</u>	<u>Estimated Measured Depth</u>
Larimer (Parkman)	3799/1111	3859
Terry (Sussex)	4554/356	4626
Hygiene (Shannon)	5104/-194	5178
Niobrara	6904/-1994	6978
Fort Hays	7156/-2246	7230
Codell	7200/-2290	7274
Greenhorn	7252/-2342	7326
Graneros	7334/-2424	7408
TD	7350	7424

Primary Objectives: Niobrara A, B, C, Codell

Secondary Objectives: Greenhorn, Larimer (Parkman)

Logging Coverage: TD to Surface (GR/Ind)  
TD to 3500' (CNL/FDC)

Cement Coverage: TD to 3500'