

FORM

2

Rev
12/05

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400312524

Date Received:

08/08/2012

PluggingBond SuretyID

20080034

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER _____
 SINGLE ZONE ☐ MULTIPLE ☒ COMMINGLE ☐

Refiling ☐Sidetrack ☐3. Name of Operator: BAYSWATER EXPLORATION AND PRODUCTION LLC4. COGCC Operator Number: 102615. Address: 730 17TH ST STE 610City: DENVER State: CO Zip: 802026. Contact Name: Corina Santos Phone: (303)928- Fax: (303)962-6237Email: csantos@petro-fs.com7. Well Name: Booth Well Number: 25-26

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 7775

WELL LOCATION INFORMATION

10. QtrQtr: NWNE Sec: 26 Twp: 7N Rng: 65W Meridian: 6Latitude: 40.551456 Longitude: -104.628972

Footage at Surface: 532 feet FNL/FSL 2336 feet FEL/FWL FEL

11. Field Name: Wattenberg Field Number: 9075012. Ground Elevation: 4894 13. County: WELD

14. GPS Data:

Date of Measurement: 03/20/2012 PDOP Reading: 1.3 Instrument Operator's Name: Brian Ritz/PFS15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL _____ FEL/FWL _____ Bottom Hole: FNL/FSL _____ FEL/FWL _____
2655 FNL 2671 FWL 2656 FNL 2665 FWL
 Sec: 26 Twp: 7N Rng: 65W Sec: 26 Twp: 7N Rng: 65W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No17. Distance to the nearest building, public road, above ground utility or railroad: 659 ft18. Distance to nearest property line: 333 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 877 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Codell	CODL		160	GWA
Greenhorn	GRNHN		160	GWA
Niobrara	NBRR		160	GWA
Parkman	PRKM		160	GWA

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

N2, Section 26, Township 7 North, Range 65 West

25. Distance to Nearest Mineral Lease Line: 532 ft 26. Total Acres in Lease: 320

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☒ Offsite ☐ Onsite **If 28, 29, or 30 are "Yes" a pit permit may be required.**

Method: ☒ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	8+5/8	24	0	690	483	690	0
1ST	7+7/8	4+1/2	11.6	0	7,775	885	7,775	3,475

32. BOP Equipment Type: ☐ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments No conductor casing will be set.; Unit Configuration: SENW and the SWNE and the NESW and the NWSE of Section 26 in T7N, R65W, 6th P.M.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Corina Santos

Title: Regulatory Technician Date: 8/8/2012 Email: csantos@petro-fs.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

API NUMBER

05

Permit Number: _____ Expiration Date: _____

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Attachment Check List

Att Doc Num	Name
400312524	FORM 2 SUBMITTED
400312705	TOPO MAP
400312706	WELL LOCATION PLAT
400312707	DRILLING PLAN
400312708	DEVIATED DRILLING PLAN
400313487	PROPOSED SPACING UNIT
400313639	30 DAY NOTICE LETTER
400314330	DIRECTIONAL DATA

Total Attach: 8 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

BMP

<u>Type</u>	<u>Comment</u>
Planning	When feasible develop multiple well sites by using directional drilling to reduce cumulative impacts and adverse impacts on wildlife resources.
Drilling/Completion Operations	When available and reasonable use a closed-loop drilling mud system to preclude the use of an earthen reserve pits when available.
Site Specific	<p>Fence the well site after drilling to restrict public and wildlife access.</p> <p>Keep well site location, the road, and the pipeline easement free of noxious weeds, litter and debris.</p> <p>Spray for noxious weeds, and implement dust control, as needed.</p> <p>Operator will not permit the release or discharge of any toxic or hazardous chemicals or wastes on Owner's Land.</p> <p>Construct and maintain gates where any roads used by operator, its employees, or contractors cross through fences on the leased premises.</p>
Storm Water/Erosion Control	<p>Use water bars, and other measures to prevent erosion and non-source pollution.</p> <p>Implement and maintain BMPs to control stormwater runoff in a manner that minimizes erosion, transport of sediment offsite, and site degradation.</p> <p>Co-locate gas and water gathering lines whenever feasible, and mitigate any erosion problems that arise due to the construction of any pipeline(s).</p>
Construction	<p>Remove only the minimum amount of vegetation necessary for the construction of roads and facilities.</p> <p>Conserve topsoil during excavation and reuse as cover on disturbed areas to facilitate regrowth of vegetation.</p> <p>No construction or routine maintenance activities will be performed during periods when the soil is too wet to adequately support construction equipment.</p>
Interim Reclamation	<p>Utilize only such area around each producing well as is reasonably necessary.</p> <p>Restore the remainder of the well site location to its original condition within a reasonable time after the completion of operations.</p> <p>All reseeding shall be done with grasses consistent with the Rocky Mountain native mix or other grasses reasonably requested by surface owner and during planting period suggested by Owner.</p>
Final Reclamation	<p>All surface restoration shall be accomplished to the satisfaction of Owner.</p> <p>All reseeding shall be done with grasses consistent with the Rocky Mountain native mix or other grasses reasonably requested by surface owner and during planting period suggested by Owner.</p> <p>Final reclamation shall be completed to the reasonable satisfaction of the Owner as soon as practical after installation (weather permitting) and in accordance with regulatory agency standards (BLM/COGCC).</p>

Total: 7 comment(s)