

Bayswater – Apollo 2012-2013 Drilling Program

Well Name: Bayswater Booth 7-26

Surface Location: 518 FNL 2326 FEL, NWNE 26 T7N R65W, Weld County, Colorado

Estimated BHL: 2030 FNL 2002 FEL, SWNE 26 T7N R65W

Estimated Elevation: GR 4894, KB 4910

Estimated Surface Casing: 690

Estimated TD: 7335

<u>Formation</u>	<u>Depth (KB)/ (Struct)</u>	<u>Estimated Measured Depth</u>
Larimer (Parkman)	3787/1123	3955
Terry (Sussex)	4542/368	4755
Hygiene (Shannon)	5092/-182	5334
Niobrara	6892/-1982	7142
Fort Hays	7144/-2234	7394
Codell	7188/-2278	7438
Greenhorn	7240/-2330	7490
Graneros	7322/-2412	7572
TD	7335	7585

Primary Objectives: Niobrara A, B, C, Codell

Secondary Objectives: Greenhorn, Larimer (Parkman)

Logging Coverage: TD to Surface (GR/Ind)
TD to 3500' (CNL/FDC)

Cement Coverage: TD to 3475'