

## Bayswater – Apollo 2012-2013 Drilling Program

Well Name: Bayswater Booth 24-26

Surface Location: 505 FNL 2316 FEL, NWNE 26 T7N R65W, Weld County, Colorado

Estimated BHL: 2654 FNL 1236 FEL, C of South Line of NE 26 T7N R65W

Estimated Elevation: GR 4893, KB 4909

Estimated Surface Casing: 690

Estimated TD: 7340

<u>Formation</u>	<u>Depth (KB)/ (Struct)</u>	<u>Estimated Measured Depth</u>
Larimer (Parkman)	3789/1121	4120
Terry (Sussex)	4544/366	4977
Hygiene (Shannon)	5094/-184	5601
Niobrara	6894/-1984	7464
Fort Hays	7146/-2236	7716
Codell	7190/-2280	7760
Greenhorn	7242/-2332	7812
Graneros	7324/-2414	7894
TD	7340	7910

Primary Objectives: Niobrara A, B, C, Codell

Secondary Objectives: Greenhorn, Larimer (Parkman)

Logging Coverage: TD to Surface (GR/Ind)  
TD to 3500' (CNL/FDC)

Cement Coverage: TD to 3475'