

## Bayswater – Apollo 2012-2013 Drilling Program

Well Name: Bayswater Booth 2-26

Surface Location: 453 FNL 2275 FEL, NWNE 26 T7N R65W, Weld County, Colorado

Estimated BHL: 690 FNL 1899 FEL, NWNE 26 T7N R65W

Estimated Elevation: GR 4892, KB 4908

Estimated Surface Casing: 690

Estimated TD: 7345

<u>Formation</u>	<u>Depth (KB)/ (Struct)</u>	<u>Estimated Measured Depth</u>
Larimer (Parkman)	3797/1111	3831
Terry (Sussex)	4552/356	4592
Hygiene (Shannon)	5102/-194	5142
Niobrara	6902/-1994	6942
Fort Hays	7154/-2246	7194
Codell	7198/-2290	7238
Greenhorn	7250/-2342	7290
Graneros	7332/-2424	7372
TD	7345	7385

Primary Objectives: Niobrara A, B, C, Codell

Secondary Objectives: Greenhorn, Larimer (Parkman)

Logging Coverage: TD to Surface (GR/Ind)  
TD to 3500' (CNL/FDC)

Cement Coverage: TD to 3500'