

## Bayswater – Apollo 2012-2013 Drilling Program

Well Name: Bayswater Booth 31-26

Surface Location: 260 FNL 2545 FEL, NWNE 26 T7N R65W, Weld County, Colorado

Estimated BHL: 1356 FNL 75 FWL, C of West Line of NW 26 T7N R65W

Estimated Elevation: GR 4893, KB 4909

Estimated Surface Casing: 690

Estimated TD: 7375

<u>Formation</u>	<u>Depth (KB)/ (Struct)</u>	<u>Estimated Measured Depth</u>
Larimer (Parkman)	3823/1086	4209
Terry (Sussex)	4578/331	5073
Hygiene (Shannon)	5128/-219	5703
Niobrara	6928/-2019	7606
Fort Hays	7180/-2271	7858
Codell	7224/-2315	7902
Greenhorn	7276/-2367	7954
Graneros	7358/-2449	8036
TD	7375	8053

Primary Objectives: Niobrara A, B, C, Codell

Secondary Objectives: Greenhorn, Larimer (Parkman)

Logging Coverage: TD to Surface (GR/Ind)  
TD to 3500' (CNL/FDC)

Cement Coverage: TD to 3500'