

Bayswater – Apollo 2012-2013 Drilling Program

Well Name: Bayswater Booth 22-26

Surface Location: 320 FNL 2498 FEL, NWNE 26 T7N R65W, Weld County, Colorado

Estimated BHL: 2658 FNL 1342 FWL, C of South Line of NW 26 T7N R65W

Estimated Elevation: GR 4893, KB 4909

Estimated Surface Casing: 690

Estimated TD: 7350

<u>Formation</u>	<u>Depth (KB)/ (Struct)</u>	<u>Estimated Measured Depth</u>
Larimer (Parkman)	3803/1106	4168
Terry (Sussex)	4558/351	5027
Hygiene (Shannon)	5108/-199	5652
Niobrara	6908/-1999	7527
Fort Hays	7160/-2251	7779
Codell	7204/-2295	7823
Greenhorn	7256/-2347	7875
Graneros	7338/-2429	7957
TD	7350	7969

Primary Objectives: Niobrara A, B, C, Codell

Secondary Objectives: Greenhorn, Larimer (Parkman)

Logging Coverage: TD to Surface (GR/Ind)
TD to 3500' (CNL/FDC)

Cement Coverage: TD to 3500'