

FORM
5A

Rev
06/12

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400314520

Date Received:

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 96850
2. Name of Operator: WPX ENERGY ROCKY MOUNTAIN LLC
3. Address: 1001 17TH STREET - SUITE #1200
City: DENVER State: CO Zip: 80202
4. Contact Name: Matt Barber
Phone: (303) 606-4385
Fax: (303) 629-8268

5. API Number 05-045-19488-00
6. County: GARFIELD
7. Well Name: Chevron TR
Well Number: 412-33-597
8. Location: QtrQtr: NENE Section: 32 Township: 5s Range: 97w Meridian: 6
9. Field Name: TRAIL RIDGE Field Code: 83825

Completed Interval

FORMATION: WILLIAMS FORK - CAMEO Status: PRODUCING Treatment Type: FRACTURE STIMULATION

Treatment Date: 09/20/2011 End Date: 09/28/2011 Date of First Production this formation: 10/09/2011

Perforations Top: 6353 Bottom: 8322 No. Holes: 159 Hole size: 0.35

Provide a brief summary of the formation treatment: Open Hole: ☐

3,500 gals 7.5% HCL; 1,031,375# 20/40 Sand; 25,378 Bbls Slickwater

This formation is commingled with another formation: ☐ Yes ☒ No

Total fluid used in treatment (bbl): 25461

Max pressure during treatment (psi):

Total gas used in treatment (mcf):

Fluid density at initial fracture (lbs/gal): 8.43

Type of gas used in treatment:

Max frac gradient (psi/ft): 0.46

Total acid used in treatment (bbl): 83

Number of staged intervals: 7

Recycled water used in treatment (bbl): 25378

Flowback volume recovered (bbl):

Fresh water used in treatment (bbl):

Disposition method for flowback: RECYCLE

Total proppant used (lbs): 1031375

Rule 805 green completion techniques were utilized: ☒

Reason why green completion not utilized:

Fracture stimulations must be reported on FracFocus.org

Test Information:

Date: 11/30/2011 Hours: 24 Bbl oil: Mcf Gas: 1274 Bbl H2O:

Calculated 24 hour rate: Bbl oil: Mcf Gas: 1274 Bbl H2O: GOR:

Test Method: Flowing Casing PSI: 1354 Tubing PSI: 1124 Choke Size: 14/64

Gas Disposition: SOLD Gas Type: DRY Btu Gas: 1050 API Gravity Oil:

Tubing Size: 2 + 3/8 Tubing Setting Depth: 8161 Tbg setting date: 10/07/2011 Packer Depth:

Reason for Non-Production:

Date formation Abandoned: Squeeze: ☐ Yes ☐ No If yes, number of sacks cmt

** Bridge Plug Depth: ** Sacks cement on top: ** Wireline and Cement Job Summary must be attached.

Comment:

--

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Matt Barber

Title: Sr. Regulatory Specialist Date: _____ Email matt.barber@wpxenery.com
:

Attachment Check List

Att Doc Num	Name
400314541	WELLBORE DIAGRAM

Total Attach: 1 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)