

Williams Production RMT Co.

Cheveron TR 412-33-597

Trail Ridge Field

SHL 1036' FNL 353' FEL (NE/4 NE/4) BHL 2062' FNL 615' FWL (SW/4 NW/4 Sec. 33-T5S-R97W)

Section 32-T5S-R97W 6th PM

Garfield County, Colorado

Formation Tops

(Measured Depths)

Mesaverde @ 5713'

Cameo @ 8014'

Rollins @ 8397'

PBTD @ 8622'

TMD @ 8671'

TVD @ 8446'

Conductor 26" Hole 16" casing/liner 80' W/135 sks cmt

Cmt @ Surface - (Cmt circ to surf during cmt job)

9 5/8" 32.3# ppf Csg. Set @ 2786'

In 12 1/4" Hole W/ 1260Sks. Cmt

Top Of Cement 4090'

6353-6567' Mesaverde
6682-6855' Mesaverde
6907-7170' Mesaverde
7199-7469' Mesaverde
7550-7790' Mesaverde
7945-8118' Mesaverde/Cameo
8165-8322' Cameo

4-1/2", 11.6 ppf. Csg. Set @ 8655' W/ 850 sks Cmt