

FORM

2

Rev
12/05

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400314257

Date Received:

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER _____
 SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refiling ☐Sidetrack ☒

PluggingBond SuretyID

20040060

3. Name of Operator: BARRETT CORPORATION* BILL4. COGCC Operator Number: 100715. Address: 1099 18TH ST STE 2300City: DENVER State: CO Zip: 802026. Contact Name: Mary Pobuda Phone: (303)312-8511 Fax: (303)291-0420Email: mpobuda@billbarrettcorp.com7. Well Name: 70 Ranch Well Number: 5-63-27-49H

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 10827

WELL LOCATION INFORMATION

10. QtrQtr: NESE Sec: 27 Twp: 5N Rng: 63W Meridian: 6Latitude: 40.368500 Longitude: -104.413170

Footage at Surface: 1946 feet FNL/FSL 165 feet FEL/FWL FEL

11. Field Name: Wattenberg Field Number: 9075012. Ground Elevation: 4594 13. County: WELD

14. GPS Data:

Date of Measurement: 10/25/2011 PDOP Reading: 1.4 Instrument Operator's Name: Adam Kelly15. If well is ☐ Directional ☒ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 900 FSL 600 FEL 900 FSL 600 FWL 900 FSL 600 FWL 900
 Sec: 27 Twp: 5N Rng: 63W Sec: 27 Twp: 5N Rng: 63W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No17. Distance to the nearest building, public road, above ground utility or railroad: 221 ft18. Distance to nearest property line: 165 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 261 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Niobrara	NBRR	GWA	320	S/2

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: _____23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No23b. If 23 is No: ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

T5N-R63W SEC 27: NW/4, SE/4, N/2SW/4, S/2SW/4; T5N-R63W SEC 23: NW/4, SE/4

25. Distance to Nearest Mineral Lease Line: 600 ft

26. Total Acres in Lease: 800

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	24	16	21	0	58	0	58	0
SURF	13+1/1	9+5/8	36	0	830	410	830	0
1ST	8+3/4	7	26	0	7,075	700	7,080	1,300
1ST LINER	6+1/8	4+1/2	11.6	0	10,843		10,843	

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments This well was sidetracked a second time because we were unable to acheive the planned build rates to land in our target in the Niobrara "C" Bench. The hole was plugged back to 5838'. A second attempt to build the curve was drilled to 6180' but we still weren't getting the necessary build angle and it was plugged back to 5844'. The third attempt was successfully kicked off at 6036' and the curve was landed at 7075' (6444' TVD) in the Niobrara "C" Bench and 7" 26#, P-110 Casing was set at 7075' and cemented back into the surface casing. The well was then drilled to the permitted TD of 10,843'MD in the Niobrara "C" Bench at the original target location. Original API# 05-123-35745.

34. Location ID: 429202

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Mary Pobuda

Title: Permit Analyst Date: _____ Email: mpobuda@billbarrettcorp.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

API NUMBER

05 123 35745 02

Permit Number: _____ Expiration Date: _____

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Attachment Check List

Att Doc Num	Name

Total Attach: 0 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)