

FORM
5Rev
02/08

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400313615

Date Received:

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 96850

4. Contact Name: Sandra Salazar

2. Name of Operator: WPX ENERGY ROCKY MOUNTAIN LLC

Phone: (303) 629-8456

3. Address: 1001 17TH STREET - SUITE #1200

Fax: (303) 629-8268

City: DENVER State: CO Zip: 80202

5. API Number 05-045-20763-00

6. County: GARFIELD

7. Well Name: Hoeppli

Well Number: RWF 312-36

8. Location: QtrQtr: SENW Section: 36 Township: 6S Range: 94W Meridian: 6

Footage at surface: Distance: 1558 feet Direction: FNL Distance: 1731 feet Direction: FWL

As Drilled Latitude: 39.485181 As Drilled Longitude: -107.839835

GPS Data:

Data of Measurement: 12/21/2011 PDOP Reading: 0.9 GPS Instrument Operator's Name: Jack Kirkpatrick

** If directional footage at Top of Prod. Zone Dist.: 1891 feet. Direction: FNL Dist.: 1163 feet. Direction: FWL

Sec: 36 Twp: 6S Rng: 94W

** If directional footage at Bottom Hole Dist.: 1910 feet. Direction: FNL Dist.: 1156 feet. Direction: FWL

Sec: 36 Twp: 6S Rng: 94W

9. Field Name: RULISON

10. Field Number: 75400

11. Federal, Indian or State Lease Number: COC07506

12. Spud Date: (when the 1st bit hit the dirt) 04/11/2012 13. Date TD: 04/18/2012 14. Date Casing Set or D&A: 04/19/2012

15. Well Classification:

☐ Dry ☐ Oil ☒ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 8702 TVD** 8662 17 Plug Back Total Depth MD 8656 TVD** 8616

18. Elevations GR 6387 KB 6413

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

RPM, CBL and MUDLOGS

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	24	18	48	0	61	23	0	61	VISU
SURF	13+1/2	9+5/8	32.3	0	1,131	320	0	1,131	VISU
1ST	7+7/8	4+1/2	11.6	0	8,692	1,230	3,674	8,692	CBL

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
WASATCH G	2,367		<input type="checkbox"/>	<input type="checkbox"/>	
MESAVERDE	4,887		<input type="checkbox"/>	<input type="checkbox"/>	
CAMEO	7,721		<input type="checkbox"/>	<input type="checkbox"/>	
ROLLINS	8,578		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

The "As-Drilled" GPS information provided is actual data of the existing well conductor location prior to the big rig spud date.

Surface Pressure = 0

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Sandra Salazar

Title: Permit Technician II

Date:

Email: Sandra.Salazar@wpenergy.com

Attachment Check List

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
400314729	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
400314723	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
400314734	DIRECTIONAL DATA	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

General CommentsUser GroupCommentComment Date

--	--	--

Total: 0 comment(s)