



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600332

Date	3/4/2012	Well Owner	Kerr McGee	Well No.	12-36	Lease	NORTHGLENN STATE
County	WELD	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (XTREME II)						
City, State, Zip	Denver, Colorado 80202						
Type of Job		Depth		Fl.	1040		
Surface	8 5/8 CSG 24"	Bottom of Surface		Fl.	1038		
Plug		Plug Landed @	993	Fl.	Time On	01.30	
Production		Pipe Landed @	1038	Fl.	Plug Down	09.45	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat TYPE III	650	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Crete 1/4 # Per Sack	20.5/209			
Mileage Charge	252	Miles		
Fuel Surcharge	252	Miles		
Additional Cement	40	SKS		
Mixing Rate	4 BPM	Pre-Flush	0946	0952
Disp. Rate	5 BPM	Mixing	0852	0930
Slurry Vol.	1.32 ³ Cu.Ft./Sk	Change Valves	0930	0933
Slurry Wt.	14.8 - 15.0 PPG	Displacement	0933	0945
Water/Cement	6.25 Gal/SK			
Water Temp.	52			
Total Slurry Vol.	162.2	BBLs Cement		
Landed Plug @	990	PSI/Final Lift @	400	PSI
Pre-Flush W/	30	BBLs H ₂ O	Tax Reference Code	Sub Total
Displace W/	63.1	BBLs H ₂ O	State CO 2.9%	Tax
Circulate	6	BBLs Cement		Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1201		Pump Truck		84			
1216/1218		Bulk Truck		84/84			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Jim Brown / Jason

Received By [Signature]
Customer or His Agent