

Bayswater – Apollo 2012-2013 Drilling Program

Well Name: Bayswater Booth 27-26

Surface Location: 255 FNL 2275 FEL, NWNE 26 T7N R65W, Weld County, Colorado

Estimated Bottom Hole Location: 75 FNL 1233 FEL, C North Line NE 26 T7N R65W

Estimated Elevation: GR 4891, KB 4907

Estimated Surface Casing: 690

Estimated TD: 7355

<u>Formation</u>	<u>Depth (KB)/ (Struct)</u>	<u>Estimated Measured Depth</u>
Larimer (Parkman)	3806/1101	3903
Terry (Sussex)	4561/346	4683
Hygiene (Shannon)	5111/-204	5239
Niobrara	6911/-2004	7039
Fort Hays	7163/-2256	7291
Codell	7207/-2300	7335
Greenhorn	7259/-2352	7387
Graneros	7341/-2434	7469
TD	7355	7483

Primary Objectives: Niobrara A, B, C, Codell

Secondary Objectives: Greenhorn, Larimer (Parkman)

Logging Coverage: TD to Surface (GR/Ind)
TD to 3500' (CNL/FDC)

Cement Coverage: TD to 3500'