



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

200329

Date <u>1/9/12</u>	Well Owner <u>PDC</u>	Well No. <u>14-16H</u>	Lease <u>MOSS</u>
Country <u>Weld</u>	State <u>Colorado</u>	Field	
Charge to <u>PETROLEUM Development Corporation</u>	ZJBS1		Charge Code
Address <u>1775 SHERMAN STREET, Suite 3000 (ENIGMO 32)</u>	For Office Use Only		
City, State <u>Denver, Colorado 80203</u>	AFE		<u>DR001316</u>
Pump Truck No. <u>1208</u>	Code	Bulk Truck No. <u>1214/1216</u>	Code
Type of Job	Depth	Ft. <u>912</u>	To
<u>surface</u> <u>9 5/8" CSG-3 1/2" 13 3/4" Hole</u>	Bottom of Surface	Ft. <u>896</u>	To
Plug	Plug Landed @ <u>851</u>	Ft.	Time On <u>1430</u>
Production	Pipe Landed @ <u>896</u>	Ft.	Time Off <u>Plug Down 1900</u>

Reference No.	Description	Qty.	Meas.	Unit Price	Amount
	Pump Truck Charge				
	Cement Neat ✓	800	SKS		
	Poz. Mix				
	Calcium Chloride	3%			
	Gel % Flo-Cele $\frac{1}{4}$ #Per Sack				
	Handling Charge				
	Hauling Charge				
	Additional Cement				
9 5/8"	Centralizers	8			80
"	Cement Basket	1			
"	Guide Shoe	1			
"	AFU FLOAT INSERT	1			
	Boxthread lock	1			
Mix Rate 4	BPM	Slurry Vol. 1.18 FT ³ /SK	Water Temp 52°F		
Disp Rate 4	BPM	Slurry WT 15.2 PPG			
Plug landed @ 700 PSI		Total Slurry Vol. 168.1 BBL Cement			
Remarks: Pre-Flush w/ 30 BBL H ₂ O		Tax Reference Code	Sub Total		
Displace w/ 165.7 BBL H ₂ O		State CO 2.9 %	Tax		
Circulate 3 BBL Cement		Disc.	Total		
Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming
1208		Pump Truck		24	
1214/1216		Bulk Truck		24/24	

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Justin, Kerry, Steve & Chris

Received By

Customer or His Agent