

FORM
5Rev
02/08

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400316245

Date Received:

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 96850

4. Contact Name: Matt Barber

2. Name of Operator: WPX ENERGY ROCKY MOUNTAIN LLC

Phone: (303) 606-4385

3. Address: 1001 17TH STREET - SUITE #1200

Fax: (303) 629-8268

City: DENVER State: CO Zip: 80202

5. API Number 05-045-20991-00

6. County: GARFIELD

7. Well Name: Jolley

Well Number: KP 323-8

8. Location: QtrQtr: SESW Section: 8 Township: 6S Range: 91W Meridian: 6

Footage at surface: Distance: 198 feet Direction: FSL Distance: 2326 feet Direction: FWL

As Drilled Latitude: 39.535536 As Drilled Longitude: -107.579792

GPS Data:

Data of Measurement: 10/07/2011 PDOP Reading: 2.1 GPS Instrument Operator's Name: J. Kirkpatrick

** If directional footage at Top of Prod. Zone Dist.: 2130 feet. Direction: FSL Dist.: 1973 feet. Direction: FWL

Sec: 8 Twp: 6s Rng: 91w

** If directional footage at Bottom Hole Dist.: 2154 feet. Direction: FSL Dist.: 1978 feet. Direction: FWL

Sec: 8 Twp: 6s Rng: 91w

9. Field Name: KOKOPELLI

10. Field Number: 47525

11. Federal, Indian or State Lease Number: COC51146

12. Spud Date: (when the 1st bit hit the dirt) 03/02/2012 13. Date TD: 03/08/2012 14. Date Casing Set or D&A: 03/10/2012

15. Well Classification:

☐ Dry ☐ Oil ☒ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 7760 TVD** 7178 17 Plug Back Total Depth MD 7703 TVD** 7121

18. Elevations GR 6526 KB 6552

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

SP/GR/HDIL/ZDL/CN AND CBL

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	24	18	48	0	68	34	0	68	VISU
SURF	13+1/2	9+5/8	32.3	0	1,443	390	0	1,443	VISU
1ST	7	4+1/2	11.6	0	7,736	1,230	4,560	7,736	CBL

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
MESAVERDE	3,782		<input type="checkbox"/>	<input type="checkbox"/>	
CAMEO	7,295		<input type="checkbox"/>	<input type="checkbox"/>	
ROLLINS	7,503		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

Please note: the "as-drilled" GPS information provided is actual data of the existing well conductor location prior to big rig spud date.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Matt Barber

Title: Sr. Regulatory Specialist Date: _____ Email: matt.barber@wpenergy.com

Attachment Check List

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
400316316	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
400316309	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
400316323	DIRECTIONAL DATA	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

General Comments

User Group	Comment	Comment Date

Total: 0 comment(s)