

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400315448

Date Received:

APPLICATION FOR PERMIT TO:

1. Drill, Deepen, Re-enter, Recomplete and Operate

2. TYPE OF WELL

OIL GAS COALBED OTHER _____
SINGLE ZONE MULTIPLE COMMINGLE

Refiling
Sidetrack

PluggingBond SuretyID

20100117

3. Name of Operator: SUNDANCE ENERGY INC

4. COGCC Operator Number: 10340

5. Address: 633 17TH STREET #1950

City: DENVER State: CO Zip: 80202

6. Contact Name: Julie L. Padilla Phone: (303)928-7128 Fax: (303)476-1645

Email: jpadilla@petro-fs.com

7. Well Name: MLD Well Number: 21-22

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 7200

WELL LOCATION INFORMATION

10. QtrQtr: NWNW Sec: 22 Twp: 4N Rng: 68W Meridian: 6

Latitude: 40.303856 Longitude: -104.993991

Footage at Surface: 854 feet FNL/FSL FNL 1350 feet FEL/FWL FWL

11. Field Name: Wattenberg Field Number: 90750

12. Ground Elevation: 4877 13. County: WELD

14. GPS Data:

Date of Measurement: 07/13/2012 PDOP Reading: 1.3 Instrument Operator's Name: Brian Ritz

15. If well is Directional Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 660 FNL 1980 FWL 660 FNL 1980 FWL
Bottom Hole: FNL/FSL 660 FNL 1980 FWL
Sec: 22 Twp: 4N Rng: 68W Sec: 22 Twp: 4N Rng: 68W

16. Is location in a high density area? (Rule 603b)? Yes No

17. Distance to the nearest building, public road, above ground utility or railroad: 780 ft

18. Distance to nearest property line: 854 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 1000 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Codell	CODL	407-87	80	E2/NW4
Niobrara	NBRR	407-87	80	E2/NW4

21. Mineral Ownership: Fee State Federal Indian Lease #: _____

22. Surface Ownership: Fee State Federal Indian

23. Is the Surface Owner also the Mineral Owner? Yes No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? Yes No

23b. If 23 is No: Surface Owners Agreement Attached or \$25,000 Blanket Surface Bond \$2,000 Surface Bond \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

NW4, N2S2 Section 22:T4N-R68W

25. Distance to Nearest Mineral Lease Line: 660 ft 26. Total Acres in Lease: 320

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? Yes No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? Yes No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? Yes No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? Yes No

31. Mud disposal: Offsite Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: Land Farming Land Spreading Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	8+5/8	24	0	550	450	550	0
1ST	7+7/8	4+1/2	11.6	0	7,200	200	7,200	6,560

32. BOP Equipment Type: Annular Preventer Double Ram Rotating Head None

33. Comments No conductor casing will be set. Exception Location Request per COGCC Rule 318A.a has been mailed to the surface owner for signature; when received the waiver will be sent to the COGCC.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? Yes No

36. Is this application part of submitted Oil and Gas Location Assessment ? Yes No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Julie L. Padilla

Title: Regulatory Manager Date: _____ Email: jpadilla@petro-fs.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

API NUMBER

05

Permit Number: _____ Expiration Date: _____

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Attachment Check List

Att Doc Num	Name
400315820	DIRECTIONAL DATA
400315821	30 DAY NOTICE LETTER
400315822	DEVIATED DRILLING PLAN
400315823	WELL LOCATION PLAT
400316208	TOPO MAP

Total Attach: 5 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

BMP

<u>Type</u>	<u>Comment</u>
Planning	When feasible develop multiple well sites by using directional drilling to reduce cumulative impacts and adverse impacts on wildlife resources.
Construction	Remove only the minimum amount of vegetation necessary for the construction of roads and facilities. Conserve topsoil during excavation and reuse as cover on disturbed areas to facilitate regrowth of vegetation .No construction or routine maintenance activities will be performed during periods when the soil is too wet to adequately support construction equipment.
Drilling/Completion Operations	When available and reasonable use a closed-loop drilling mud system to preclude the use of an earthen reserve pits when available.
Site Specific	Fence the well site after drilling to restrict public and wildlife access. Keep well site location, the road, and the pipeline easement free of noxious weeds, litter and debris. Spray for noxious weeds, and implement dust control, as needed. Sundance Energy Inc., will not permit the release or discharge of any toxic or hazardous chemicals or wastes on Owner's Land. Construct and maintain gates where any roads used by Sundance Energy Inc., its employees, or contractors cross through fences on the leased premises.
Storm Water/Erosion Control	Use water bars, and other measures to prevent erosion and non-source pollution. Implement and maintain BMPs to control stormwater runoff in a manner that minimizes erosion, transport of sediment offsite, and site degradation. Co-locate gas and water gathering lines whenever feasible, and mitigate any erosion problems that arise due to the construction of any pipeline(s).
Interim Reclamation	Utilize only such area around each producing well as is reasonably necessary. Restore the remainder of the well site location to its original condition within a reasonable time after the completion of operations. All reseeding shall be done with grasses consistent with the Rocky Mountain native mix or other grasses reasonably requested by surface owner and during planting period suggested by Owner.
Final Reclamation	All surface restoration shall be accomplished to the satisfaction of Owner. All reseeding shall be done with grasses consistent with the Rocky Mountain native mix or other grasses reasonably requested by surface owner and during planting period suggested by Owner. Final reclamation shall be completed to the reasonable satisfaction of the Owner as soon as practical after installation (weather permitting) and in accordance with regulatory agency standards (BLM/COGCC).

Total: 7 comment(s)