

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400311638

Date Received:

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refiling ☐

Sidetrack ☐

PluggingBond SuretyID

20100017

3. Name of Operator: ENCANA OIL & GAS (USA) INC

4. COGCC Operator Number: 100185

5. Address: 370 17TH ST STE 1700

City: DENVER State: CO Zip: 80202-5632

6. Contact Name: JENNIFER LIND Phone: (720)876-5890 Fax: (720)876-6890

Email: JENNIFER.LIND@ENCANA.COM

7. Well Name: IONE Well Number: 1C-2H

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 12080

WELL LOCATION INFORMATION

10. QtrQtr: NWNE Sec: 2 Twp: 2N Rng: 66W Meridian: 6

Latitude: 40.173440 Longitude: -104.739810

Footage at Surface: 419 feet FNL/FSL 1347 feet FEL/FWL FEL

11. Field Name: WATTENBERG Field Number: 90750

12. Ground Elevation: 5078 13. County: WELD

14. GPS Data:

Date of Measurement: 07/27/2012 PDOP Reading: 1.7 Instrument Operator's Name: RICE

15. If well is ☐ Directional ☒ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 597 FNL 1417 FEL 460 FSL 1450 FEL 460
Sec: 2 Twp: 2N Rng: 66W Sec: 2 Twp: 2N Rng: 66W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 1175 ft

18. Distance to nearest property line: 419 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 91 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBRR		640	GWA

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

T2N-R66W-SEC.2: ALL; SEC.4: S/2; SEC.8: NE/4, SW/4; SEC.10: E/2, NW/4

25. Distance to Nearest Mineral Lease Line: 460 ft

26. Total Acres in Lease: 1760

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	22	16	30	0	80	80	80	0
SURF	12+1/4	9+5/8	40	0	916	249	916	0
1ST	8+3/4	7	26	0	7,854	963	7,854	616
2ND	6+1/8	4+1/2	13.5	0	12,080	373	12,080	7,554

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments ENCANA REQUESTS THE APPROVAL OF A RULE 318A(l).a.1 AND 318A(l).c.1 EXCEPTION LOCATION AS THE WELL HEAD WILL BE LOCATED OUTSIDE A GWA DRILLING WINDOW AND FURTHER THAN 50' FROM AN EXISTING WELL - REQUEST LETTER AND WAIVERS ATTACHED. ENCANA ALSO REQUESTS THE OMISSION OF OPEN HOLE LOGS - REQUEST LETTER ATTACHED. ENCANA ALSO REQUESTS THE APPROVAL OF A RULE 318A.m. EXCEPTION LOCATION AS THERE IS AN EXISTING WELL THAT FALLS WITHIN 150' OF THE PROPOSED LATERAL - REQUEST LETTER ATTACHED, NO WAIVER REQUIRED AS THE EXISTING WELL IS OPERATED BY ENCANA. PROPOSED SPACING UNIT IS T2N-R66W-SEC.2: ALL. ENCANA PLANS TO DRILL 13 HORIZONTAL WELLS SPACED ACROSS SECTION 2 AND BELIEVE THIS CONFIGURATION WILL EFFECTIVELY DRAIN THE 640 ACRE SPACING UNIT. ENCANA WILL COMPLY WITH COGCC POLICY FOR BRADENHEAD MONITORING DURING HYDRAULIC FRACTURING TREATMENTS IN THE GREATER WATTENBERG AREA DATED MAY 29, 2012.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: JENNIFER LIND

Title: REGULATORY ANALYST Date: _____ Email: JENNIFER.LIND@ENCANA.

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

API NUMBER

05

Permit Number: _____ Expiration Date: _____

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Attachment Check List

Att Doc Num	Name
400316718	DEVIATED DRILLING PLAN
400316720	DIRECTIONAL DATA
400316721	EXCEPTION LOC REQUEST
400316722	EXCEPTION LOC REQUEST
400316723	EXCEPTION LOC WAIVERS
400316726	PROPOSED SPACING UNIT
400316727	OTHER
400316728	MINERAL LEASE MAP
400316731	TOPO MAP
400316734	30 DAY NOTICE LETTER
400316736	WELL LOCATION PLAT

Total Attach: 11 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)