

FORM  
5Rev  
02/08

## State of Colorado

## Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400267669

Date Received:

04/24/2012

## DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 8960

4. Contact Name: Bryan Brown

2. Name of Operator: BONANZA CREEK ENERGY OPERATING COMPANY

Phone: (720) 440-6100

3. Address: 410 17TH STREET SUITE #1400

Fax: (720) 279-2331

City: DENVER State: CO Zip: 80202

5. API Number 05-123-34979-00

6. County: WELD

7. Well Name: Wetco Farms

Well Number: M-4

8. Location: QtrQtr: NENW Section: 4 Township: 4N Range: 63W Meridian: 6

Footage at surface: Distance: 1350 feet Direction: FNL Distance: 2647 feet Direction: FWL

As Drilled Latitude: 40.345000 As Drilled Longitude: -104.442850

## GPS Data:

Data of Measurement: 04/17/2012 PDOP Reading: 1.5 GPS Instrument Operator's Name: Adam Kelly

\*\* If directional footage at Top of Prod. Zone Dist.: 2716 feet. Direction: FNL Dist.: 2611 feet. Direction: FWL

Sec: 4 Twp: 4N Rng: 63W

\*\* If directional footage at Bottom Hole Dist.: 2716 feet. Direction: FNL Dist.: 2611 feet. Direction: FWL

Sec: 4 Twp: 4N Rng: 63W

9. Field Name: WATTENBERG

10. Field Number: 90750

11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 03/24/2012 13. Date TD: 03/29/2012 14. Date Casing Set or D&amp;A: 03/30/2012

## 15. Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 6878 TVD\*\* 6691 17 Plug Back Total Depth MD 6869 TVD\*\* 6682

18. Elevations GR 4566 KB 4592

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

## 19. List Electric Logs Run:

CBL, GAMMA RAY, HRI, CDL, CNL

## 20. Casing, Liner and Cement:

## CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
SURF	12+1/4	8+5/8	24	0	732	520	0	732	CALC
1ST	7+7/8	4+1/2	11.6	0	6,869	594	2,070	6,878	CBL

## STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____					
Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom
Details of work:					

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES					
FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
SHARON SPRINGS	6,366		<input type="checkbox"/>	<input type="checkbox"/>	
NIOBRARA	6,458		<input type="checkbox"/>	<input type="checkbox"/>	
FORT HAYS	6,686		<input type="checkbox"/>	<input type="checkbox"/>	
CODELL	6,710		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

--

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Bryan Brown

Title: Drilling EIT Date: 4/24/2012 Email: bbrown@bonanzacrk.com

### Attachment Check List

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
400276363	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
400276362	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
400267669	FORM 5 SUBMITTED	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400267769	LAS-TRIPLE COMBINATION	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400276358	LAS-CEMENT BOND	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400276359	LAS-CEMENT BOND	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400276360	DIRECTIONAL DATA	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400310985	DIRECTIONAL DATA	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

**General Comments**

<b><u>User Group</u></b>	<b><u>Comment</u></b>	<b><u>Comment Date</u></b>
Permit	Off Hold attached directional template per operator.	7/31/2012 8:33:52 AM
Permit	On Hold. Missing directional template.	7/31/2012 7:26:15 AM
Permit	Bryan Brown is not a designated agent for Bonanza	7/25/2012 8:30:33 AM

Total: 3 comment(s)