



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600438

Date	03-23-12	Well Owner	Kerr McGee	Well No.	22-36	Lessee	NORTHGLENN STATE
County	WELD	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (XTREME #11)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth		Fl.	1053		
Surface	8 5/8" CSG-24"	Bottom of Surface		Fl.	1043		
Plug		Plug Landed @	999	Fl.	Time On	1745	
Production		Pipe Landed @	1043	Fl.	Plug Down	2015	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat TYPE III 100% EXCESS	660	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Cete 1/4 # Per Sack				
Mileage Charge	246	Miles		
Fuel Surcharge	246	MILES		
Additional Cement	40	SKS		
Mixing Rate 4 BPM	Pre-Flush 1924	1931		
Disp. Rate 5 BPM	Mixing 1931	2000		
Slurry Vol. 1.32 ³ Cu.Ft./Sk	Change Valves 2000	2003		
Slurry Wt. 14.8 - 15.0 PPG	Displacement 2003	2015		
Water/Cement 6.25 Gal/SK				
Water Temp. 62°F				
Total Slurry Vol. 164.5	BBLS Cement			
Landed Plug @ 400	PSI/Final Lift @ 250	PSI		
Pre-Flush W/ 30	BBLS H ₂ O	Tax Reference Code	Sub Total	
Displace W/ 63.5	BBLS H ₂ O	State CO 2.9%	Tax	
Circulate 6	BBLS Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1208		Pump Truck		82			
1209-1214		Bulk Truck		82-82			

We do not assume any responsibility for any damage or conditions resulting from our service. All work is subject to review and decision.

Delivered By JUSTIN, EVAN, STEVE, CHRIS

Received By

[Signature]
Customer or His Agent