



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600429

| | | | | | | | |
|-----------------|--|-------------------|------------|----------|----------------|-------|------------------|
| Date | 03-19-12 | Well Owner | Kerr McGee | Well No. | 40-310 | Lease | NORTHGLENN STATE |
| County | WELD | State | Colorado | | | | |
| Charge to | Kerr McGee Oil & Gas Onshore, LP | | | | | | |
| Address | 1999 Broadway, Suite 3700 (XTREME #11) | | | | | | |
| City, State Zip | Denver, Colorado 80202 | | | | | | |
| Type of Job | | Depth | Ft. 1045 | | | | |
| Surface | 8 3/8" CSG-24 # | Bottom of Surface | Ft. 1035 | | | | |
| Plug | | Plug Landed @ | 991 | Fl. | Time On 1500 | | |
| Production | | Pipe Landed @ | 1035 | Fl. | Plug Down 1745 | | |

| Description | Qty. | Meas. | Unit Price | Amount |
|--|--------------------|-----------|------------------------|--------|
| Set Up Charge | 1 | | | |
| Cement Neat TYPE III 100% EXCESS | 650 | SKS | | |
| Poz. Mix | | | | |
| Calcium Chloride | 2.5 | % | | |
| Gel % Flo-Crete 1/4 # Per Sack | | | | |
| Mileage Charge | 240 | Miles | | |
| Fuel Surcharge | 240 | MILES | | |
| Additional Cement | 40 | SKS | | |
| Mixing Rate 4 BPM | Pre-Flush | 1654 | 1701 | |
| Disp. Rate 5 BPM | Mixing | 1701 | 1730 | |
| Slurry Vol. 1.32 ³ Cu.Ft./Sk | Change Valves | 1730 | 1733 | |
| Slurry Wt. 14.8 - 15.0 PPG | Displacement | 1733 | 1745 | |
| Water/Cement 6.25 Gal/SK | | | User ID ZDSB4 | |
| Water Temp. 52°F | | | WBSA/NOICC 2051212 DRL | |
| Total Slurry Vol. 162.2 BBLs Cement | | | G/L Apct. 80012090 | |
| Landed Plug @ 925 PSI/Final Lift @ 425 PSI | | | | |
| Pre-Flush W/ 30 BBLs H ₂ O | Tax Reference Code | Sub Total | | |
| Displace W/ 63.0 BBLs H ₂ O | State CO 2.9% | Tax | | |
| Circulate 4 BBLs Cement | | Total | | |

| Truck No. | Code | State Mileage | Nebraska | Colorado | Wyoming | Other | Total Mileage |
|-----------|------|---------------|----------|----------|---------|-------|---------------|
| 1208 | | Pump Truck | | 80 | | | |
| 1216-1217 | | Bulk Truck | | 80-80 | | | |

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By JUSTIN, EVAN, STEVE, CHRIS

Received By

Customer or His Agent