

FORM 5A

Rev 06/12

State of Colorado Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Table with columns DE, ET, OE, ES

Document Number: 400319354

Date Received:

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 96850
2. Name of Operator: WPX ENERGY ROCKY MOUNTAIN LLC
3. Address: 1001 17TH STREET - SUITE #1200
City: DENVER State: CO Zip: 80202
4. Contact Name: Sandra Salazar
Phone: (303) 629-8456
Fax: (303) 629-8268

5. API Number 05-045-21061-00
6. County: GARFIELD
7. Well Name: Duggan
Well Number: RWF 321-32
8. Location: QtrQtr: NENW Section: 32 Township: 6S Range: 94W Meridian: 6
9. Field Name: RULISON Field Code: 75400

Completed Interval

FORMATION: WILLIAMS FORK - CAMEO Status: PRODUCING Treatment Type: FRACTURE STIMULATION

Treatment Date: 03/20/2012 End Date: Date of First Production this formation: 03/22/2012

Perforations Top: 5899 Bottom: 7810 No. Holes: 128 Hole size:

Provide a brief summary of the formation treatment: Open Hole: []

3501 Gals 7 1/2 % HCL; 543300 # 30/50 Sand; 85500 100 Mesh; 17427 Bbls Slickwater (Summary)

This formation is commingled with another formation: [] Yes [X] No

Total fluid used in treatment (bbl): 20928 Max pressure during treatment (psi):

Total gas used in treatment (mcf): Fluid density at initial fracture (lbs/gal): 8.43

Type of gas used in treatment: Max frac gradient (psi/ft): 0.85

Total acid used in treatment (bbl): 3501 Number of staged intervals: 6

Recycled water used in treatment (bbl): 17427 Flowback volume recovered (bbl):

Fresh water used in treatment (bbl): Disposition method for flowback:

Total proppant used (lbs): 628800 Rule 805 green completion techniques were utilized: [X]

Reason why green completion not utilized:

Fracture stimulations must be reported on FracFocus.org

Test Information:

Date: 05/31/2012 Hours: 24 Bbl oil: 0 Mcf Gas: 1091 Bbl H2O: 0

Calculated 24 hour rate: Bbl oil: 0 Mcf Gas: 1091 Bbl H2O: 0 GOR: 0

Test Method: Flowing Casing PSI: 1910 Tubing PSI: 1755 Choke Size: 10/64

Gas Disposition: SOLD Gas Type: DRY Btu Gas: 1037 API Gravity Oil: 0

Tubing Size: 2 + 3/8 Tubing Setting Depth: 7585 Tbg setting date: 04/04/2012 Packer Depth:

Reason for Non-Production:

Date formation Abandoned: Squeeze: [] Yes [] No If yes, number of sacks cmt

** Bridge Plug Depth: ** Sacks cement on top: ** Wireline and Cement Job Summary must be attached.

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Sandra Salazar

Title: Permit Technician II Date: _____ Email: sandra.salazar@wpenergy.com
:

Attachment Check List

Att Doc Num	Name
400319362	WELLBORE DIAGRAM

Total Attach: 1 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)