

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400272726

Date Received:

07/11/2012

PluggingBond SuretyID

20030009

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER _____
SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refiling ☐

Sidetrack ☐

3. Name of Operator: NOBLE ENERGY INC

4. COGCC Operator Number: 100322

5. Address: 1625 BROADWAY STE 2200

City: DENVER State: CO Zip: 80202

6. Contact Name: SUSAN MILLER Phone: (303)228-4246 Fax: (303)228-4286

Email: smiller@nobleenergyinc.com

7. Well Name: CECIL FARMS PC

Well Number: I06-68-1HN

8. Unit Name (if appl):

Unit Number:

9. Proposed Total Measured Depth: 11668

WELL LOCATION INFORMATION

10. QtrQtr: 2 Sec: 6 Twp: 6N Rng: 66W Meridian: 6

Latitude: 40.522930

Longitude: -104.813990

Footage at Surface: 255 feet FNL/FSL 259 feet FEL/FWL
FNL FEL

11. Field Name: Wattenberg

Field Number: 90750

12. Ground Elevation: 4880

13. County: WELD

14. GPS Data:

Date of Measurement: 01/24/2012 PDOP Reading: 1.7 Instrument Operator's Name: Brian Brinkman

15. If well is ☐ Directional ☒ Horizontal (highly deviated) submit deviated drilling plan.

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL
993 FNL 794 FEL 990 FNL 535 FWL
Sec: 6 Twp: 6N Rng: 66W Sec: 6 Twp: 6N Rng: 66W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 243 ft

18. Distance to nearest property line: 255 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 327 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Niobrara	NBRR		320	GWA

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

Please see attached plat and lease descriptions. Also attached is a copy of the Surface Use Agreement. Noble Energy Inc certifies that the lease(s) shall be committed to the unit.

25. Distance to Nearest Mineral Lease Line: 0 ft

26. Total Acres in Lease: 769

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☒ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: CLOSED LOOP

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	18+1/2	16		0	100	6	100	0
SURF	13+3/4	9+5/8	36	0	910	419	910	0
1ST	8+3/4	7	26	0	7,605	532	7,605	0
1ST LINER	6+1/8	4+1/2	11.6	7500	11,668			0

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments First string top of cement will be 200' above the Niobrara formation. The production liner will be hung off inside of the 7" casing. This is a single horizontal well with production facilities to be located on location. unit configuration N/2. The waiver language for twinning and outside the window is included in the submitted SUA.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: SUSAN MILLER

Title: Regulatory Analyst III

Date: 7/11/2012

Email: smiller@nobleenergyinc.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____

Director of COGCC

Date: 8/22/2012

API NUMBER

05 123 35998 00

Permit Number: _____ Expiration Date: 8/21/2014

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1)Note surface casing setting depth change from 850' to 910'. Increase cement coverage accordingly and cement to surface.
- 2)Provide notice of MIRU via an electronic Form 42.
- 3)Comply with Rule 317.i and provide cement coverage from the end of the production casing to a minimum of 200' above the Niobrara. Verify coverage with a cement bond log.

Operator must meet Water Well Testing requirements as per amended Rule 318Ae(4)

Operator must comply with COGCC Policy for Bradenhead Monitoring During Hydraulic Fracturing Treatments in the Greater Wattenberg Area dated May 29, 2012.

Attachment Check List

Att Doc Num	Name
2113803	EXCEPTION LOC REQUEST
2481739	SURFACE CASING CHECK
400272726	APD APPROVED
400272736	30 DAY NOTICE LETTER
400284498	WELL LOCATION PLAT
400284500	DEVIATED DRILLING PLAN
400284501	DIRECTIONAL DATA
400304840	PROPOSED SPACING UNIT
400304841	PROPOSED SPACING UNIT
400304842	MINERAL LEASE MAP
400304843	LEGAL/LEASE DESCRIPTION
400304844	PROPOSED SPACING UNIT
400304845	SURFACE AGRMT/SURETY
400319145	FORM 2 SUBMITTED

Total Attach: 14 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Final Review Completed. No LGD or public comment received.	8/9/2012 11:25:01 AM
Permit	Operator requests approval of a Rule 318Aa and Rule 318Ac exception location: Wellhead is to be located outside of a GWA drilling window and will be located more than 50' from an existing well location. Request and waivers attached. Ready to pass pending public comment 8/2/12.	7/17/2012 1:17:29 PM
Permit	Attached Exception location request. Waiver is part of SUA. Corrected spacing unit objective and added to opr comments as per opr.	7/17/2012 11:45:31 AM

Total: 3 comment(s)

BMP

<u>Type</u>	<u>Comment</u>
Material Handling and Spill Prevention	Spill Prevention Control and Countermeasures (SPCC) plans are in place to address any possible spill associated with Oil & Gas operations throughout the state of Colorado in accordance with CFR 112.
General Housekeeping	General housekeeping will consist of neat and orderly storage of materials and fluids. Wastes will be temporarily stored in sealed containers and regularly collected and disposed of at offsite, suitable facilities. If spills occur, prompt cleanup is required to minimize any commingling of waste materials with stormwater runoff. Routine maintenance will be limited to fueling and lubrication of equipment. Drip pans will be used during routine fueling and maintenance to contain spills or leaks. Any waste product from maintenance will be containerized and transported offsite for disposal or recycling. There will be no major equipment overhauls conducted onsite. Equipment will be transported offsite for major overhauls. Cleanup of trash and discarded materials will be conducted at the end of each work day. Cleanup will consist of patrolling the roadway, access areas, and other work areas to pick up trash, scrap debris, other discarded materials, and any contaminated soil. These materials will be disposed of properly.
Drilling/Completion Operations	<p>Anti-collision: Prior to drilling operations, Operator will perform an anti-collision scan of existing offset wells that have the potential of being within close proximity of the proposed well. This anti-collision scan will include definitive MWD or gyro surveys of the offset wells with included error of uncertainty per survey instrument, and compared against the proposed wellpath with its respective error of uncertainty. If current surveys do not exist for the offset wells, Operator may have gyro surveys conducted to verify bottomhole location. The proposed well will only be drilled if the anti-collision scan results indicate that there is not a risk for collision, or harm to people or the environment. For the proposed well, upon conclusion of drilling operations, an as-constructed gyro survey will be submitted to COGCC with the Form 5.</p> <p>During and Post stimulation:</p> <p>Noble Energy Inc. will comply with the COGCC Policy for Bradenhead Monitoring During Hydraulic Fracturing Treatments in the Greater Wattenberg Area dated 5/29/12.</p>
Storm Water/Erosion Control	Stormwater management plans (SWMP) are in place to address construction, drilling and operations associated with Oil & Gas development throughout the state of Colorado in accordance with Colorado Department of Public Health and Environment (CDPHE) and General Permit No. COR-038637. BMP's will be constructed around the perimeter of the site prior to, or at the beginning of construction. BMP's used will vary according to the location and will remain in place until the pad reaches final reclamation.

Total: 4 comment(s)