

FORM  
5Rev  
02/08

## State of Colorado

## Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

2287005

Date Received:

01/18/2012

## DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 10301

4. Contact Name: GARY HAEFELE

2. Name of Operator: DEJOUR ENERGY (USA) CORPORATION

Phone: (303) 296-3535

3. Address: 1401 17TH STREET #1000

Fax: (303) 296-3888

City: DENVER State: CO Zip: 80202

5. API Number 05-103-11810-00

6. County: RIO BLANCO

7. Well Name: FEDERAL

Well Number: 36-24A

8. Location: QtrQtr: LOT 2 Section: 36 Township: 1N Range: 103W Meridian: 6

Footage at surface: Distance: 685 feet Direction: FSL Distance: 1328 feet Direction: FWL

As Drilled Latitude: 40.007770 As Drilled Longitude: -108.909660

## GPS Data:

Date of Measurement: 01/24/2012 PDOP Reading: 1.8 GPS Instrument Operator's Name: K TESKY

\*\* If directional footage at Top of Prod. Zone Dist.: feet. Direction: Dist.: feet. Direction:

Sec: Twp: Rng:

\*\* If directional footage at Bottom Hole Dist.: feet. Direction: Dist.: feet. Direction:

Sec: Twp: Rng:

9. Field Name: WILDCAT

10. Field Number: 99999

11. Federal, Indian or State Lease Number: COC-065852

12. Spud Date: (when the 1st bit hit the dirt) 06/10/2011 13. Date TD: 14. Date Casing Set or D&amp;A: 06/18/2011

## 15. Well Classification:

☐ Dry ☐ Oil ☒ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 3865 TVD\*\* 17 Plug Back Total Depth MD 3820 TVD\*\*

18. Elevations GR 5487 KB 5499

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

## 19. List Electric Logs Run:

GR/CCL/CBL, GR/SP/CALIPER/RESISTIVITY/DPHZ/NPOR, DIPOLE SONIC

## 20. Casing, Liner and Cement:

## CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	20	14		0	80	100	0	80	CALC
SURF	12+1/4	8+5/8		0	522	410	0	522	CALC
1ST	7+7/8	4+1/2		0	3,860	640	80	3,860	CBL

**STAGE/TOP OUT/REMEDIAL CEMENT**

Cement work date: \_\_\_\_\_

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

21. Formation log intervals and test zones:

**FORMATION LOG INTERVALS AND TEST ZONES**

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
MESAVERDE	0	2,402	<input type="checkbox"/>	<input type="checkbox"/>	
CASTLEGATE	2,402	2,524	<input type="checkbox"/>	<input type="checkbox"/>	
MANCOS	2,524	3,574	<input type="checkbox"/>	<input type="checkbox"/>	MANCOS SHALE NOT OFFERED ON PULLDOWN.
MANCOS B	3,574	3,674	<input type="checkbox"/>	<input type="checkbox"/>	
SHALE	3,674	3,863	<input type="checkbox"/>	<input type="checkbox"/>	MANCOS SHALE NOT OFFERED ON PULLDOWN. MANCOS CAN ONLY BE ENTERED ONCE.

Comment:

FORM 5A DOC#2287006

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: GARY HAEFELE

Title: OPERATIONS MGR Date: 1/13/2012 Email: GHAEFELE@DEJOUR.COM

**Attachment Check List**

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
1533448	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Directional Survey **	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
2287005	FORM 5 SUBMITTED	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

**General Comments**

User Group	Comment	Comment Date
Permit	off hold: rec'd cmt. tkt. and logs.	7/27/2012 3:13:50 PM
Permit	oper. submitted as drilled GPS	7/23/2012 8:24:05 AM
Permit	on hold--need as drilled GPS, digital and paper logs, surf. cmt. tkt.	2/9/2012 8:57:40 AM

Total: 3 comment(s)