



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600447

Date	4/11/2012	Well Owner	Kerr McGee	Well No.	1N-29H2	Lease	WARDEN
County	WELD	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (MAJOR #42)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth		FL	934		
Surface	9 5/8" CSG 3/4" 13 1/2" HWC	Bottom of Surface		FL	923		
Plug		Plug Landed @	878	FL	Time On	1730	
Production		Pipe Landed @	923	FL	Plug Down	2130	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat TYPE III	690	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Crete 1/4 # Per Sack				
Mileage Charge	150	Miles		
Fuel Surcharge	150	Miles		
Additional Cement		SKS		
Mixing Rate 4 BPM	Pre-Flush	1928	1934	
Disp. Rate 5 BPM	Mixing	1934	2114	
Slurry Vol. 1.32 ³ Cu.Ft./Sk	Change Valves	2114	2117	
Slurry Wt. 14.8 - 15.0 PPG	Displacement	2117	2130	
Water/Cement 6.25 Gal/SK				
Water Temp. 57				
Total Slurry Vol. 162.2	BBLS Cement			
Landed Plug @ 960	PSI/Final Lift @ 375	PSI		
Pre-Flush W/ 30	BBLS H ₂ O	Tax Reference Code	Sub Total	
Displace W/ 67.8	BBLS H ₂ O	State CO 2.9%	Tax	
Circulate 5	BBLS Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1201		Pump Truck		50			
1234/1217		Bulk Truck		50/50			

800/2090

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By J. F. ADAM/J. F. WIL

Received By R. J. Case
Customer or His Agent